

Mobile Home Park Permit

Permit No.	MHP00001
Registered Owner	1251719 BC Ltd.
Applicant	Sean Carroll, Core Group Civil Consultants Ltd.
Subject Property	9090 Trans-Canada Highway
Description of Land	
• Parcel Identifier	009-885-200
• Folio No.	15038.000
• Legal Description	The East 60 Acres of Section 10, Range 5, Chemainus District, Except 16.5 Foot Strip Along and Adjoining the North and East Boundaries thereof, Reserved for Road Purposes, Except Parts in Plans 11489, 26194 and VIP68870
Number of Park Units	101
Source of Water	Municipal
Sewage Disposal Method	Septic

Conditions of Permit

1. This permit is issued subject to compliance with all relevant Municipality of North Cowichan bylaws, including Mobile Home Parks Bylaw No. 1775 and Zoning Bylaw 1997, No. 2950.
2. This permit applies to the land described above and hereinafter called "the Land."
3. The Land shall be developed in accordance with **Development Permit No. DP000256** issued by the Municipality of North Cowichan on **November 2, 2022**, and filed under **Registration No. CB318246** with the Land Title and Survey Authority of British Columbia and the following schedules"
 - **Schedule 1 - MHP00001 - Sewage Disposal Island Health - TRAX Developments Ltd. June 9, 2021 (22 pages)**
 - **Schedule 2 - MHP00001 - Sewage Disposal Island Health - TRAX Developments Ltd. May 1, 2023 (4 pages)**
 - **Schedule 3 - MHP00001 - Landscaping Plan and Security - PMG Landscape Architects May 16, 2022 (8 pages)**
 - **Schedule 4 - MHP00001 - Servicing Plan - Modular Home Development Core Group August 17, 2023 (23 pages)**

- **Schedule 5 - MHP00001 - Civil Schedule B - Core Group February 21, 2023 (4 pages)**
 - **Schedule 6 - MHP00001 - Stormwater Management Memo, Schedule B - Geopacific June 1, 2021 (6 pages)**
 - **Schedule 7 - MHP00001 - Retaining Wall Drawing, Schedule B and EGBC Assurances November 20, 2023 (10 pages)**
4. A portion of the Land is in the Agricultural Land Reserve. The use and development of this portion of Land for the Mobile Home Park must comply with the Agricultural Land Commission's **Reasons for Decision, Resolution No. 366/2022** issued on **October 11, 2022**, and all relevant policies and regulations of the Agricultural Land Commission.
 5. This permit is not a building permit. A valid building permit must be obtained prior to construction and / or placement of any modular dwelling unit or accessory structure on the property.
 6. Further to page 1 of Schedule 7, retaining wall(s) proposed along lots 39 to 48 must be constructed as per the "Single Tier Walls" typical design, or as otherwise determined by the "Engineer of Record".
 7. The agreed landscaping security in the amount of \$143,332.48 has been receipted. As per the provided November 8, 2023, Core Group Consultants letter of agreement, no partial drawdown of security (monies held for duration of project) will be permitted until completion of the entire project's landscaping installation.
 8. The Municipality reserves the right to observe installations and testing of any aspect of the servicing for this project; and review certifications including confirmation from Island Health for sewage collection, treatment, and disposal.
 9. Pursuant to Section 2.02 (h) of the Mobile Home Parks Bylaw No. 1775, if after issuance of this permit the authorized construction has not commenced within six months from the date of the Mobile Home Park approval, or if, after the commencement of a period of six months through any cause other than weather conditions, strikes or lockouts, or if the work be not carried on continuously and in a bonafide manner this permit shall be void, and the work shall not again commence until a new permit has been issued and fee paid.

Date of Mobile Home Park Permit Approval/Issuance by Council or its

Delegate: This permit was approved and issued on **January 31, 2024**.

This permit will expire on **July 31, 2024**.

The Corporation of the District of North Cowichan



Tim Byron,
Chief Building Inspector

TRAX DEVELOPMENTS LTD.

Box 9-6, Thetis Island, BC, V0R2Y0. T 250-246-4774 Fx 866-424-8569
onsite@traxdev.com

4/28/2021


RE: 9090 Trans Canada Highway sewerage system servicing

This is to confirm that intend designing, and the developer intends constructing, onsite sewerage systems compliant with the BC *Health Act* Sewerage System Regulation to provide sewerage servicing for the proposed phased development of this site.

The proposed development is to be phased. Each phase is to be served with a separate sewerage system, collecting wastewater from the individual dwelling units within that phase, treating this wastewater and discharging it to ground. Each phase is expected to be of such a size that the design daily domestic sewage flow for each separate system will be below 22,700 Litres.

Please do not hesitate to contact the undersigned for clarification.

Sincerely



Ian Ralston P.L.Eng
TRAX



RECORD OF SEWERAGE SYSTEM

		Filing # (OFFICE USE ONLY) <i>DC 21/144</i>	
1. Property Information	<input checked="" type="checkbox"/> New Construction	<input type="checkbox"/> Alteration	<input type="checkbox"/> Repair
			<input type="checkbox"/> Amendment – Original Filing #
	Tax Assessment Roll # PID provided.		PID # 009-885-200
	Legal Description (Plan, Lot, District Lot, Block Numbers) <small>THE EAST 60 ACRES OF SECTION 10, RANGE 5, CHEMAINUS DISTRICT, EXCEPT 16.5 FOOT STRIP ALONG AND ADJOINING THE NORTH AND EAST BOUNDARIES THEREOF, RESERVED FOR ROAD PURPOSES, EXCEPT PARTS IN PLAN</small>		
Street (Civic) Address or General Location 9090 Trans Canada Highway		City Chemainus	
2. Owner Information	Name of Legal Owner 1230226 B.C. LTD		Mailing Address C/O TRAX Developments Ltd. Box 9-6
	Phone 250-246-4774	City Thetis Island	Prov BC
			Postal Code V0R2Y0
3. Authorized Person Information	Name of Authorized Person Ian Ralston		Mailing Address Box 9-6
	Phone 250-246-4774	City Thetis Island	Prov BC
			Postal Code V0R2Y0
	Registration # 158292	Email onsite@traxdev.com	
4. Structure Information	Sewerage System Will Serve:		
	<input type="checkbox"/> Single Family Dwelling <input type="checkbox"/> Other Structure (specify) _____ <input checked="" type="checkbox"/> Other Dwelling (specify) 20 Modular homes		
	The sewerage system is designed for an estimated minimum daily domestic sewage flow of (check one) <input type="checkbox"/> Less than or equal to 9,100 litres <input checked="" type="checkbox"/> More than 9,100 litres but less than 22,700 litres		
5. Site Information	Depth of native soil to seasonal high water table or restrictive layer (cm) 140 cm, see specs		Information respecting the type, depth and porosity of the soil (sand media) is attached <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
	GPS Location of System (decimal degrees) Latitude N 48.89984996643548 Longitude W -123.71886581048344		
	Horizontal Accuracy (m) 10		<input checked="" type="checkbox"/> Recreational GPS <input type="checkbox"/> Differential GPS
6. Drinking Water Protection	Will the sewerage system be located less than 30 m from a water well? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
	If yes, attach a professional's report and specify the intended distance _____ (m)		
	Distance of proposed sewerage system to the closest body of surface water >30 m to permanent fresh water (m)		
7. System Information	Sewerage treatment method <input checked="" type="checkbox"/> Type 1 <input type="checkbox"/> Type 2 <input type="checkbox"/> Type 3		
8. Legal or Regulatory Considerations	<input checked="" type="checkbox"/> Construction of the proposed sewerage system will not conflict with legal instruments registered on the property. <i>See specifications</i>		Is this filing submitted as the result of an order from the Health Authority? <input type="checkbox"/> Yes (attach a copy of the order) <input checked="" type="checkbox"/> No
9. Plot Plan and Specifications	Plot Plan (to scale) and specifications are attached <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
	<input checked="" type="checkbox"/> The plans and specifications are consistent with Standard Practice Source of Standard Practice: <input checked="" type="checkbox"/> Ministry of Health Standard Practice Manual <input type="checkbox"/> Other See design notes		
10. Authorized Person's Signature	Signature 		OFFICE USE ONLY
	Date 7 June 2021	Filing Accepted Date June 9/21	
			Receipt Number # 200100 # 255743


TRAX DEVELOPMENTS LTD.

SEWERAGE SYSTEM DESIGN NOTES AND SUMMARY SPECIFICATIONS




Design	9090 TCH Phase 1	Friday, June 4, 2021
Revision	Rev. 0	Client: Core Group Civil Consultants
Notes	System selection and design based primarily on SPM V3 (September 2014) and supporting rationale and calculations (on file). See references for other sources of standard practice utilized.	

Introduction and objectives	<p>The owner intends construction of a sewerage system with STEP collection and central dispersal to serve a first 20 home phase of a proposed mobile home park on this site. TRAX has been retained by the client on behalf of the owner to provide a design of the sewerage system. This sewerage system will be owned and managed by the owner. Later phases are to be served by separate systems, which will be designed and filed separately at the time of development of those phases.</p> <p>Objective of this report is to provide a suitable design for a Sewerage System including dispersal area on this site to serve the use defined below. Preliminary site and soil evaluation was carried out by Ian Ralston P.L. Eng and Henry VanHelle ROWP (site and soil evaluation summary report attached) and serves as the basis for this design. See also plans (R0) which are based on survey and development plans provided by the client. Prior to and during installation, the design engineer may approve design changes. The design engineer and installer will prepare as-built drawings and specifications to confirm these changes.</p> <p>Construction must be supervised (field review of installation) by TRAX, this will be by the design engineer (Ian Ralston) or a subordinate under direct supervision. Prior to installation the design engineer will specify the minimum requirements for field review, shop drawing review and for notification of TRAX.</p> <p>Unspecified or contradictory installation details should be confirmed with TRAX (the design engineer). Certain items must be confirmed with TRAX prior to or at installation or may be redesigned during installation by TRAX; these are noted in these specifications or in the plans.</p> <p>For general installation, maintenance, monitoring and operation practice the installation is to follow the SPM V3</p> <p>Limitations</p> <p>This design and site evaluation report is subject to the attached Statement of General Conditions.</p> <p>By accepting and using this report the owner and client acknowledge that the capacity of the system is limited to the stated design flows of wastewater with characteristics representative of normal residential sewage.</p>
Domestic water supply well setback	<p>Client reports, and site evaluation did not identify any domestic water supply wells within 30 m of proposed sewerage system components. The area is served by municipal water supply.</p> <p>Prior to installation, the installer is to confirm that no domestic water supply wells are located within 30 m of any proposed sewerage system component. If a well is found closer than this specified distance, the design engineer is to be informed and construction is to cease until instructions are provided.</p>
Preliminary design	<p>This is a preliminary design, and may be revised prior to or during system installation. Certain items must be confirmed prior to or during construction, as identified in the drawings and specifications.</p>
STEP collection system mains and pumps, water main setback	<p>As site grading plans may change prior to construction the specification of STEP collection pumps and forcemains is preliminary and must be confirmed and detailed prior to construction. The client will take responsibility for detailed installation specification and construction of the STEP mains and STEP connection valves, in coordination with TRAX.</p> <p>All sewerage system components, including the STEP mains, are to be set back a minimum of 3 m to the proposed municipal water main that will run down new roadways. The civil drawings are to specify risk management requirements for situations where the STEP piping must cross water lines, and this must be acceptable to the Public Health Engineer.</p>
Summary of regulatory context	<p>Other sewerage systems will be installed on the site, to serve other sources of wastewater or other phases. This system is to be completely separate from those systems, and is to serve only the sources identified in this design. It is not to be physically connected at any point to other sources of wastewater or other sewerage systems existing or planned on the site.</p> <p>The Ministry of Health and Ministry of Environment have provided a policy document clarifying the application of regulations for onsite sewerage systems, the <i>Onsite Sewerage Jurisdictional Flow Divide Interpretation Guideline</i>. Based on that policy document, each separate sewerage system (whether on the same lot or not) must be filed under the Sewerage System Regulation if the system has a daily design flow of less than 22,700 L/day and discharges to ground—which is the case for this system. Following this policy, we have designed this system following the Sewerage System Regulation and standard practice as defined by that regulation.</p> <p>Following this regulatory policy, standard practice and the above noted observations we have developed a design with the characteristics described below.</p>
Attached	<p>Drawings.</p> <p>Float setting sheet for pump chambers.</p> <p>Site and soil evaluation summary.</p>




Lot legal	<p>Note that lot legal may change.</p> <p>THE EAST 60 ACRES OF SECTION 10, RANGE 5, CHEMAINUS DISTRICT, EXCEPT 16.5 FOOT STRIP ALONG AND AJJOINING THE NORTH AND EAST BOUNDARIES THEREOF, RESERVED FOR ROAD PURPOSES, EXCEPT PARTS IN PLANS T1489, 26194 AND V1P68870</p>		
PID	009-885-200 (current)	Easements or Covenants?	<p>Title on file. An existing development permit is in place, we understand that a new permit will replace this. If any requirements of the new permit affect the sewerage system construction, contact the design engineer for revisions to this design.</p> <p>An easement is in place for a water main (see plan), the water main is proposed to be relocated, and this design includes requirements for water line setbacks.</p> <p>Other easements are in place, relating to use of parts of the southern part of the property by the adjacent property. These are not relevant to the proposed system placement.</p>
Development permit or environmentally sensitive areas	<p>Any and all development permissions necessary for construction of the sewerage system and for connected facilities are the responsibility of the owner. We understand that development approval by the Municipality of North Cowichan may be required, if these include requirements related to the system contact the design engineer for revisions to this design to address such requirements.</p> <p>The proposed dispersal area falls partly within a reportedly required buffer strip to the development external property lines, we understand from the client that this is acceptable and have relied upon the client's opinion for siting the dispersal beds in this area. Note that tree cover is to be maintained in the bed area.</p>		
Owners	1230226 B.C. LTD		
		Address	9090 Trans Canada Highway, Chemainus (civic address may change)




SYSTEM SELECTION

Item	Value	Constraint, opportunity, result	Solution and rationale
Site, soils and site use			
Use (existing and planned)	Type of use	Mobile home	Per each of 20 mobile homes
	Number of bedrooms	3	Typical, with water conserving fixtures and appliances.
	Floor area (sq m)	140	Typical maximum.
Occupants		3.75	per Table II-9
DDF Table II-9 (L/day)	Occupancy	1125	Per each mobile home
DDF other (L/day)			SPM design flows utilized to allow use of SPM standard loading rates.
Effluent strength		Normal residential	No garburators, large tubs or water filter/softener backwash water to flow to the system.
Chosen DDF (L/day)		22500	For the 20 mobile homes in Phase 1. ADF = 11250 L/day on a weekly average basis.
Soil texture (<2 mm fraction)	Sandy Loam	Fine Sands, Loamy Fine Sands, Sandy Loams	
Structure	Subangular Blocky	F	Table II-4
Structure grade	Strong		
Consistence	Very Friable		
Coarse fragment %	3%	No HLR adjustment	s. III-4.1.2.2
Coarse fragment type	Gravel		
Different soil for LLR?	No		
Other soil notes			Underlying Till shows high measured permeability.
Kfs or Perc to be used?	Kfs	Kfs	
Kfs (mm/day)	1320	1320	
Kfs for LLR selection (mm/day)		1320	
Soil depth (cm)	140		Based on TP4 and 5 plus geotechnical pits.
Slope %	20%		
Slope shape, location		Ridge, Convex Linear	
Temperature	Low frost risk		
Net positive evapotranspiration, mm/yr?	0	No ET, ETA, Lagoons	Tree cover to be retained and or enhanced. ET based on Farmwest data.
Rainfall, mm/year	1039	No HLR adjustment	Duncan Forestry Environment Canada climate normals.
System selection and loading rates			
Soil constraints?	Table II-5	Type 1 VS 90cm Type 2 VS 120cm Dosed to sequential trenches or pressure manifold only (unless ET, ETA, lagoon)	Pressure distribution to be used to sand media bed system to address limited available area.
	Table II-5 notes	No further constraints	Manual check for VS, AIS
	Table II-6	Seepage Beds, sand lined beds and bottomless sand filters Not allowed	Sand mounds OK
	Table II-6 notes	No further constraints	See above for ET, ETA and Lagoon net positive ET constraints.
	Table II-7 notes	No further constraints	Opportunity due to higher permeability in underlying Till.
Soil depth and VS options, distribution and dosing options	Type 1, gravity dist.	90	Pressure distribution to be used to sand media bed system to address limited available area.
	Type 1, micro dosing to sand media bed system. Table II-17	Native soil 25 cm Sand 30 cm Total 60 cm	
	Selected option, minimum as constructed	Native soil 120 cm Sand 30 cm Total 150 cm	Custom VS, performance based rationale on file considering custom contour loading rate and performance in VS for custom HS as well as a check on system performance and to support the use of VS monitoring as a surrogate for soil treatment performance.



Horizontal separation constraints?	Breakout (to beds)	3 m	Expected minimum 7.5 m to surface breakout to meet SPM standards, risk of breakout at as close as 3 m considered in case of flow of part of percolate toward east and breakout on road cut. Custom, performance based, rationale on file following EGBC guidelines.
	Property lines (external, to beds)	1 m	From bed. Lines to be surveyed. Note that greater spacing may be necessary to keep toe area fill within property line.
	Tanks to property lines (internal to development)	0 m	STEP tanks may be placed on internal property lines.
	Water mains to tanks and piping	3 m	Meets SPM standards. For any crossing pipes, refer to civil drawings and specifications.
	Other setbacks	To meet SPM standards	
HLR for Type 2 or sand media system basal area (mm/day)	Table II-22:	50	
	Table II-23:	60	
	Adjusted:	50	Adjustment for coarse fragment content and or rainfall not needed
	Selected HLR:	50	
HLR for Type 1 to sand media system (mm/day)	Table II-24 sand type:	Sand filter coarse sand	
	Table II-24 HLR:	50	
	Selected HLR:	50	
Minimum system contour length	VS for LLR (cm)	120	
	Table II-26	Use LLR tables	
	Table II-27 (L/day/m)	130	
	Table II-28 (L/day/m)	200	
	Tabular LLR (L/day/m)	130	
	Selected LLR (L/day/m)	634	Custom HLLR based on Darcy Law calculation, on file. For Phase 1 system conservatively based on receiving area to west of system only and not considering flow in underlying Till soils. Note that natural discharge capacity for incident rainfall assumed to be provided by native soils and Till with water table mounding per existing observed conditions.
	Min. length, m	35.5	
Length constraint?	Max. contour length available (m)	38	
	Bed length for AIS (m)	38	
Dispersal area size options	Native soil, Type 2 AIS (square metres)	450	
	Sand mound, Type 1 AIS to sand (sq m)	450	
	Type 1 sand mound option, width of sand bed (m)	11.58	For single bed.



Dispersal area sizing and system summary (further system selection rationale on file)


Dispersal area sizing	Sand Media system, Type 1	
	Type of system	Sand mound
	Type of sand	Sand filter coarse sand
	Bed width (m)	3.6
	Bed length (m)	38
	Number of beds	4
	Bed spacing (m)	2
	Resultant HLR (mm/day)	46
	Number of laterals	6
	Lateral spacing (m)	0.6
	Grade rise at bed width (m)	0.72
	Minimum bed spacing (m)	1.44
	Basal area needed beyond bed area (sqm)	0
	Vertical separation & dose	
	Native soil (cm)	120
	Sand media (cm)	30
	Total constructed (cm)	150
	Type of distribution	Uniform
	Type of dosing	Micro dosing
	Soil or sand media type for dosing specification	Sand filter coarse sand
	Sand media system?	Yes
	Effluent type for dose spec.	1
	Soil or sand depth for micro dosing selection (cm)	30
	Dosing frequency (SPM)	28
	Dosing frequency (specified)	28
	Pressure distribution	
	Dose volume (L)	804
	Number of zones	10
	Dose volume per zone (L)	80.4
	(usgal)	21
	Design HLR (mm/day)	46
	Center or end fed?	End
	Lateral length (m)	13.5
	Number of laterals (total for all zones)	60
	Number of laterals per zone	6
	Lateral diam. (inches)	1.25
	Lateral type	Sch 40 PVC
	Manifold diam. (inches)	2
	Manifold type	Sch 40 PVC
	At Grade Bed?	No
	Min. orifice number for all zones	874
	Chosen orifice number	900
	Orifices per zone	90.0
	Orifices per lateral	15.0
	Nominal spacing (cm)	96
	Orifice size (inches)	5/32
	Design method	Orencia Pump Select
	Pump operating point, usgpm	88
	Pump TDHR, ft.	58
	Distal pressure (ft.)	7 ft target
	Laterals drain?	No
	Pump run time per dose (s)	15
	Doses per day total for all zones	150
	STD to peak factor	2
	Timer interval, STD (mins)	10

ISLAND HEALTH
ENGINEERING

JUN 09 2021


This filing Does Not Constitute
Approval for Further Subdivision

	Timer interval, PEAK (mins)	5	At DDF, before alarm
	Run time per day (mins) at DDF	70	For all zones
Other considerations			
	Chosen receiving and filter tank size	5000 IG	With final filtration to 1/16".
	Chosen STEP septic tank size (L)	80000	Chosen tank size: 2500 IG, shared by two modular homes. Pump out tank with demand dose pumping from second chamber of tank. First chamber volume 8077 L Total STEP tank volume 80,000 L
	Minimum septic tank size (L)	67500	For Type 1 system
System summary	Treatment	Type 1 with effluent filter	Final filtration in addition to filtration at each STEP tank
	Flow equalization	Micro timed dosing	No dosing above DDF, large flow equalization capacity.
	Dispersal	Pressure distribution to sand media bed	Custom sand media bed design.
	Summary of site use and capability constraints addressed by specified system	Simplest system to meet site constraints, avoiding use of treatment plant system to improve overall reliability.	




SPECIFICATIONS


Piping and installation of pipelines	<p>Install all piping to meet Plastic Pipe and Fittings Association and SPM standards and guidelines, with pipe bedding and backfill to meet appropriate MMCD standards for the location. Pipeline minimum cover 45 cm, 60 cm in travelled areas. Bed pipes with pre-approved bedding sand and compact, min. 15 cm bedding around pipes. Where piping is below traffic areas, sleeve piping and consult project civil engineers for backfill and compaction requirements. Ensure groundwater flow concentration will not occur in pipeline trenches, using trench dams as necessary (confirm dam and any associated drainage details with project civil engineer).</p> <p>All pipeline trenches to be marked for detection. Install tape at 4" below grade above drip forcemain or flush main lines. For lines not installed in same trench as cables install with tracer wire. Provide a 12 AWG PE jacketed copper clad steel tracer wire (example PRO-TRACE HF-CCS PE30). Install tracer wire at 15cm above pipelines. Bring tracer wire into terminal valve boxes and connection boxes with a 1.5 m slack loop (without breaking cable) to provide access for tracing. ground both ends of tracer cable in accessible location with disconnect at distal end, provide minimum 1.5 m long leads for connection. If splices are necessary, use manufacturer recommended water resistant splices, insulated with electrical tape (minimize splices).</p> <p>Tank interconnection piping PVC Sch40 solvent weld. Fully support interconnection piping.</p> <p>Ensure all components are separated by min. 3 m from water supply piping, or relocate or sleeve water supply piping as necessary.</p> <p>All valve boxes with "sewer" lids and pea gravel bases. Mark each box location with 5 ft upright length of 1/2" EMT conduit or pre approved equal.</p> <p>Where pipelines must cross bare rock or areas with very shallow soil, pipelines may be bedded and filled over with pre approved fill. Cover to be minimum 30 cm settled depth. In all cases vegetation is to be established over trenched areas or filled areas as rapidly as practical, and biodegradable erosion control matting is to be used in the interim.</p>
Valve boxes	<p>Install all valve boxes in landscaped areas, or contact design engineer for revised specifications.</p> <p>Plastic valve boxes, sized as needed for adequate access or as per the drawings. All valve boxes to be bedded on and around with 10 mm washed pea gravel, with the base of the box supported on a minimum of 10 cm depth of pea gravel.</p> <p>All valve boxes with tamper resistant lids marked "sewer" or with purple lids. Boxes over electrical splice boxes marked "electrical". Mark boxes for detection with 60 cm section of 16 mm rebar installed vertically in the valve box. Where necessary utilize concrete blocks to support valve box bases per MMCD standards to ensure piping or dripline is not impacted by valve box settling, even where direct foot pressure is applied to the valve box.</p>
STEP collection tanks, one shared by two modular homes	<p>Septic tank Dams Precast 2500 IG, with first compartment as septic tank and second as pump chamber. With standard 4" PVC solvent weld inlet tee, effluent filter at outlet of first compartment. Second compartment with no outlet (pump discharge via riser). Compartment divider sealed to lid to prevent scum carry over. Access risers all 24" diameter, with separate riser for pump compartment, do not place risers over compartment divider.</p> <p>Effluent filter Polylok A100 12 x 20 with alarm (Polylok filter alarm switch, SJE Rhombus Tank Alert Duo XT alarm panel) and base support.</p> <p>Provide design engineer with shop drawings of tanks for review prior to tanks being poured.</p> <p>The STEP tanks are shown schematically in the drawings, final location of the tanks is to be pre approved by the design engineer in coordination with the project civil and structural engineers, taking into account sewer locations from the modular homes and with the structural engineer's review of tank excavation near the modular home pads and necessary separation to avoid the tank location affecting either tanks or pads structurally.</p>
STEP collection tanks, pump discharge system	<p>Second compartment of 2500 IG tank as STEP pump chamber, nominal capacity 720 IG. Pump discharge via riser. Venting via effluent filter to septic tank.</p> <p>Second compartment of STEP tank with pump system, Myers 10MD05121 (120V) pump with discharge assembly per drawings. Note discharge orifice, orifice sizing to be confirmed with design engineer based on final elevations during construction.</p> <p>Pump controlled by demand dosing using SJE Rhombus Dual Float Assembly (120V) set to dose with pump on at 7" above inside base of tank and off at 6".</p> <p>Alarm float SJE Rhombus HO sensor float, set at 18" above inside base of tank to float on (allowing > 1 day DDF alarm reserve in pump compartment). Floats supported on site built float tree constructed of 1.25" Sch40 PVC pipe supported on base of tank and clipped to riser with Sintech orifice shield (shield screwed to riser with two of #10x1.5" stainless steel screws), floats attached using SJE Rhombus clips and all stainless steel hose clamps. Provide adequate wire to allow removal of float tree and pump from tank without disconnection.</p> <p>Alarm from high level float and effluent filter float to SJE Rhombus Tank Alert Duo panel mounted on pressure treated 4x4" post at tank with small roof over to protect from direct rainfall. Panel set at 36" above final grade. Effluent filter alarm to amber lamp, pump tank high level alarm to red lamp.</p> <p>All electrical work to BC Electrical Code.</p> <p>Pump discharge and electrical connection via riser, seal pipe penetration with grommet with Sikaflex 1a sealant backup. Electrical connections through SJE Rhombus 2" cord seal assembly and hub, with 2" conduit to above grade splice box. Use waterproof plastic box, mount on same post as alarm panel and protect with same roof.</p> <p>Discharge to connection to STEP forcemain through 1.25" IPS SDR9 HDPE (pump drop) pipe, no joints. Transitions at ends of pipe constructed using 1.25" MIP x barb, stainless steel Boshart transitions installed with two of all stainless steel hose clamps per fitting. At pump tank transition to be installed into stainless steel ball valve at outlet of pump discharge assembly. At connection check valve transition to be installed with stainless steel 1.25" union and stainless steel threaded nipple to check valve.</p> <p>Provide and hold on site spare STEP pump and one set of all discharge assembly and control components.</p>
STEP collection system mains	<p>STEP collection main sizing to be confirmed by design engineer in coordination with project civil engineers. Preliminary sizing 2" IPS SDR11 HDPE for both mains. Install pipe with all fusion or socket fusion welded fittings, all transitions to PVC with flange fittings with stainless steel bolts. Project civil engineers to detail specification of STEP mains and connections, ensuring provision of cleanouts and, at connections, 1.25" connection plumbing with all stainless ball valve and serviceable stainless steel flap type check valve (FIP) per connection in suitable valve boxes located as shown on the plan drawing.</p> <p>STEP mains to discharge individually to inlet of first final receiving septic tank (ST-1) via minimum 3 m length of 4" PVC Sch40 solvent weld pipe, transitioning with flange fitting and with true union PVC ball valve per main.</p> <p>Design engineer to be retained to review shop drawings and/or proposed drawings and specifications prior to construction of STEP mains and connections.</p>




Central receiving septic tanks ST-1 and ST-2	<p>Dans Precast 2500 IG, single compartment. Two tanks in series.</p> <p>First tank with normal inlet and outlet tees, second with inlet tee and effluent filter at outlet.</p> <p>Effluent filter Polylok A300 12 x 28 with alarm (Polylok filter alarm switch, SJE Rhombust Tank Alert XT alarm panel) and base support.</p> <p>Secondary effluent filter, Polylok A100 8x18 with base support. Install with invert of outlet at normal tank inlet elevation. Wye outlet pipes together outside tank.</p> <p>Note outlet riser and dual outlet boots must be placed to allow installation of both filters through riser.</p> <p>Provide design engineer with shop drawings of tanks for review prior to tanks being poured.</p>
Central equalization tanks EQ-1 and EQ-2	<p>Dans Precast 5100 IG, two tanks. Manifold at base (with rubber boots at base of tank end wall) and at inlet elevation, tanks with inlet and outlet boots at standard inlet elevation.</p> <p>Manifold pipes enter tanks through rubber boots. Encase in non shrinking grout at entry prior to embedding in anti flotation flange concrete pour for vault.</p> <p>Ensure invert of base manifold pipe is level to internal base of tanks.</p> <p>Lower tank section with anti-flotation flange. The tank lower section is to be provided with anti-flotation base by the manufacturer, with rebar extending from these bases. Note that the anti-flotation base adds approximately 5 cm (2") to the tank height.</p> <p>At installation the rebar is to be bent down parallel to the ground surface and concrete is to be poured to provide minimum 7.5 cm below and 7.5 cm above the rebar and to form a flange minimum 60 cm around the tank base.</p> <p>Concrete is to be minimum 20 MPa.</p> <p>Provide total of 6 of 24" risers in tanks to allow placement of two pumps per riser plus one riser for transducer and float controls.</p> <p>Provide design engineer with shop drawings of tanks for review prior to tanks being poured.</p>
Tank installation	<p>Ensure equalization tanks are placed to maintain all discharge fortetains below dispersal bed elevations.</p> <p>All tanks to be installed to good engineering practice and per manufacturer standards. See note below for bedding. Ensure all pipe connections are fully supported. See below for information on tank bedding and pipe protection.</p> <p>All tanks to be installed with minimum 5 cm drainrock or pea gravel base below tank.</p> <p>Tank connections to be made with 4" Sch40 PVC pipe. Sanitary tees in tanks may use PVC DWV fittings, ensure fittings allow for proper tank venting. If Fernco couplings are used ensure installed with stainless steel shear rings. To reduce risk of floating for the tanks tank area is to be effectively drained to the site stormwater system, with a drainage system that will lower water table during wet season conditions to at least below 30 cm above the base of the lowest tank or if not practical for the equalization tanks, at least below the mid tank joint for the equalization tanks. Provide the design engineer with shop drawings showing proposed drainage system details and elevations for pre approval. Note that stormwater system design is the responsibility of the site civil engineers.</p> <p>At the tank area provide an 8" diameter PVC pipe installed from the base of the lowest tank in the area (or near the outlet end of each STEP tank) to just below final grade, with pea gravel around the base slotting. The base of the pipe is to be capped and side slotted for 15 cm from the bottom of the pipe, and the top provided with a cleanout cover with drilled vent hole per SPM standards. This pipe may be used to inspect water table level in the tank area prior to tank pump out.</p> <p>Tank areas are to be protected from traffic.</p>
Tank installation, lid joint sealing	<p>After tank lid or upper part is installed and mastic fully settled, seal inside and out of lid joint using Sikaflex 1a sealant following manufacturer guidelines. Back up seal on inside by grouting lid with non shrinking grout.</p>
Tank bedding	<p>Free draining material is to be used as bedding around pipelines, sewers, tanks, tank connections and tank risers and, where tank cover is 50 cm or greater, for a minimum 15 cm depth over the tank lid top. This free draining material is to be hydraulically connected to the tank area drainage system allowing any incoming water to drain away from tanks to the site stormwater system.</p> <p>This free draining material may be birds eye gravel, 6 or 10 mm washed pea gravel, 19 mm washed round drain rock (pea gravel or drain rock to meet SPM standards) or compacted pre-approved washed bedding sand (compacted to minimum 95% standard proctor density) or other pre-approved material which will maintain adequate permeability after compaction. In all cases piping is to be bedded in bedding sand or other pre-approved granular pipe bedding material.</p> <p>Where pipes enter or leave risers, place pipes on top of the concrete tank lid and in traffic areas embed in minimum 10 cm concrete if cover over tank is less than 50 cm (see separate note with respect to electrical conduit).</p> <p>Where the tank excavation is based on broken rock or other coarse materials the design engineer may specify graded aggregate to blind the rock, or non-woven geotextile as a separation layer. The contractor is to allow for a Nutex 4553 geotextile layer covering up to 25% of the sides and base of the excavation, and the same material between drain rock and any bedding sand as a separation layer if a graded filter with pea gravel is not used as a separation layer.</p> <p>Note that pea gravel and drain rock must be compacted with a vibratory compactor or vibration using a rod system to ensure that the material is fully settled.</p> <p>All upslope run on and stormwater is to be diverted away from the tank area.</p>
Tank access	<p>All tanks with with Orenco riser bases cast into the lid with no internal concrete lip. Install UltraRib 24" riser pipe, secure to bases with PL Premium adhesive and min. 4 of #10 stainless steel screws installed from inside the adapter. Riser with TuffTite lids with stainless steel screws.</p> <p>Riser lids to be min. 5 cm above final grade, slope grade away from risers. Except where below manhole covers, in which case lid top to be at maximum elevation practical without interfering with the manhole cover.</p> <p>Each riser is to be provided with a TuffTite lid with seal, secured with stainless steel screws to the UltraRib pipe.</p> <p>All riser penetrations must be sealed with grommets backed up with Sikaflex 1a sealant or pre-approved equal.</p> <p>Note that equipment access is to be provided within 15 cm of the top of risers.</p>
Tank watertight testing.	<p>Tanks to be tested for water tightness of tank and of tank/riser connections and the connection from the equalization tank to pump vault, after installation but before tank interconnection and backfill. Follow the procedure described in the SPM V2 Appendix O.</p> <p>Inlet and outlet of tanks should be capped or caps inserted in the rubber boots. Do not fill more than 2.5 cm above top of tank lid.</p> <p>Maximum leakage in 24 hours after 24 hour presoak 0.1% of volume. Measure fall in riser adapter by marking adapter at water level. Do not attempt to measure fall in tank itself. Report results to design engineer and do not backfill tanks until design engineer has confirmed that leakage rate meets standard.</p>



Ventling, for central receiving and pump tanks.	<p>4" Sch40 PVC, install with no single fitting over 45 degrees to allow for cleaning.</p> <p>Provide stainless steel insect screen at tank riser exit to reduce risk of insects or sludge entering vent pipes.</p> <p>From first receiving tank outlet riser and one pump tank riser for each pump tank on top of tank lid, slope pipe up to vent exit to odor biofilter to allow condensate to drain to tank. Minimum 0.1% slope. Use DWV sanitary tees or wyes for connection of tanks.</p> <p>See drawings for vent biofilter.</p> <p>Provide shop drawings for pre approval.</p>
Float and level settings	To be confirmed prior to commissioning based on final layout. Preliminary settings attached.
Discharge pumps	<p>Confirm pump selection with designer at layout prior to installation.</p> <p>Preliminary specification:</p> <p>One pump per zone, total of 10 pumps. Installed with two pumps per riser in equalization tanks.</p> <p>Pumps Monarch (Little Giant) WS1001BA-12-20 with 2" discharge (240 VAC 13.6 FLA, pump height 13.75"), install with PVC Sch 80 2" Y-ball check valve vertically at pump outlet, 2" Sch 40 PVC pipe riser, 2" Sch 80 PVC slip 90 and 2" PVC double block true union ball valve (ball valve installed horizontally, with max. 15 cm from valve to top of riser), 2" PVC Sch 40 force main exits pump chamber through side of riser on top of tank lid.</p> <p>Pump run time approx. 15 seconds per dose.</p> <p>Provide and hold on site one spare discharge pump and one set of pump discharge assy. components.</p>
Discharge pump control system	<p>Confirm with designer at layout prior to installation.</p> <p>Preliminary specification:</p> <p>Custom 10 zone panel (with level controls) with individual pump timer settings per zone, with standards and override settings for timed dosing. With pump datalogging. With external alarm strobe. In waterproof housing. If custom panel to be utilized, provide design engineer with shop drawings for review prior to order.</p> <p>Alternate option, utilize SJE Rhombus EZI duplex panel with C-sensor level control and redundant high and low level floats. EZI SW104C3A3E4A4D6A10E17D29B30A22G With pump relay output taken to custom 10 zone switching relay with separately adjustable time down relays to allow individual on times per zone. Resulting in a total of 10 zones with one pump per zone.</p> <p>Floats (redundant high and low) SJE Rhombus NO sensor floats, externally weighted, 20' cord. Supported on SJE Rhombus stainless steel float brackets or pre approved site built brackets.</p>
Electrical installation	<p>The sewerage system design does not include electrical engineering services and any specifications or notes related to electrical components or installation are for information on preferred approach, and for guidance, only. Where there is a difference between the specifications or notes and the Code, the Code is to be followed.</p> <p>All floats and pump cables to be led to external splice boxes through 2" rigid PVC conduit, utilize 2" or 2.5" (depending on number of cables) SJE Rhombus cord seal assemblies to seal and provide strain relief at riser penetration. Any splices in tanks to be heat shrink sealed, with cable sheath sealed with secondary heat shrink.</p> <p>Ensure c-sensor transducer cable is led in separate conduit to control panel, and fully shielded. Any splices to be soldered and shielded. Do not run in close proximity to line voltage conduits.</p> <p>Where practical, place waterproof splice boxes above grade, where not practical ensure valve boxes over splice boxes are adequately drained and bring conduit vertically up into base of valve box to the water proof splice box. Confirm splice box location and detail is acceptable to the client and to the electrical inspector prior to installation.</p> <p>All panels are to be protected by surge suppression either in the panel or at the electrical supply.</p>
Force main and manifold system	<p>Confirm with designer at layout prior to installation.</p> <p>Preliminary specification:</p> <p>Force main, 2" Sch 40 PVC with Sch 80 PVC fittings, taken from pump to end of each dispersal system zone, force main continues as manifold. Note that design engineer may specify 3" PVC mains for upper dispersal area bed zones, where 3" PVC used transition to and from 2" with reducing couplings.</p> <p>Force main to be installed below manifold elevation, does not drain to field after dose. Place bentonite or other low permeability plugs in force main trench to prevent flow concentration in trench. Force main to feed up to manifold with 90 deg. elbow at end of manifold. Install force main on undisturbed mineral soil.</p> <p>Manifold (2" Sch 40 PVC) feeds bed system single zone from end of zone. Cleanout to grade (using Simtech STF-111L-200 long radius sweep, extension pipe as required and male adapter with threaded PVC cap) in 10" round valve box at end of manifold. Valve box with min. 2 cu ft pea gravel base.</p> <p>At each lateral 2" x 1.25" Sch 40 PVC slip tee, and 1.25" slip PVC sch 40 ball valve to lateral.</p> <p>Ensure force main and manifold fully supported to reduce risk of differential settling.</p> <p>All valves in valve boxes marked "sewer" and with pea gravel base.</p>
Dispersal area and distribution system	<p>Confirm with designer at layout prior to installation.</p> <p>Preliminary specification:</p> <p>10 zone pressure distribution system. Upper beds (1 and 2) with two zones, lower beds (4 and 5) with three zones.</p> <p>Beds (360 cm wide) with distribution system laid out 6 laterals wide, lateral spacing 60 cm (30 cm to edge of pea gravel bed). Laterals at nominal 13 to 15 m length per lateral.</p> <p>Lateral lines 1.25" Sch 40 PVC, install lateral pipes level to ± .5 cm over length of bed. Level from lateral to lateral as well as along length of each lateral.</p> <p>Orifices 5/32" at approx. 95 cm on center, confirm number with design engineer at final layout, min. 30 cm from all orifices to edge of bed, all orifices face up.</p> <p>For average zone 15 orifices per each lateral, confirm for each zone at final layout. Target distal pressure 7 ft. min. Cover orifices with Simtech STF-106TDS-125-1.50 orifice shields. Each lateral with cleanout at distal end, cover cleanouts with 10" diameter valve boxes based in the pea gravel bed and embedded around with pea gravel. Form cleanouts using Simtech STF-111L-125 long radius sweeps, PVC Sch 40 MIP x slip and PVC threaded cap (all 1.25").</p> <p>Each lateral with ball valve (for isolation during flushing) at proximal end, cover ball valves with 10" round valve boxes per cleanout boxes.</p> <p>Two bed observation ports installed to base of pea gravel bed to SPM standards for each bed. Cover with 10" diameter valve boxes.</p> <p>Flush laterals at commissioning, minimum 12 gallons flush per.</p>



Sand media	<p>Base of sand media to be placed on prepared native soil following SPM sand mound standards and guidelines.</p> <p>Design engineer to be retained to inspect and pre-approve soil moisture content prior to bed preparation, and the prepared bed prior to sand placement.</p> <p>Sand media is to meet SPM Coarse Sand Filter Sand specifications and is to be pre-approved by TRAX.</p> <p>The sand must be kept clean during installation.</p> <p>Install sand media following SPM sand mound standards and guidelines after scarification, establish minimum settled sand depth of 30 cm above scarified basal area and level top of sand media by raising sand depth at downslope side of bed.</p> <p>Material testing:</p> <p>Sand delivered to the site is to be checked by the installer using a jar test for each load delivered to confirm sand is clean, with <4% silt and clay. In addition the installer may retain sand samples from each truckload delivered.</p>
Dispersal system distribution bed	<p>Distribution bed to be installed level. Bed to be centered on sand media bed, and sand media is to be placed around bed. Wood forms may be used for bed construction.</p> <p>Aggregate 10 mm washed pea gravel meeting SPM standards, minimum depth below laterals 10 cm. Minimum 5 cm above laterals. Cover pea gravel with min. 5 cm SPM specification Mound sand prior to placing cover soil, create cross slope from centerline of bed using sand to raise center of bed cover per section drawing. Do not cover bed with filter fabric. Cover soil to meet SPM standards, may be pre approved soil from the site. Cover soil to be vegetated with lawn grass.</p> <p>At final layout the design engineer may approve stepping the bed between two zones, if this is done a pre approved membrane must be installed vertically between the ends of the two zone's pea gravel beds, extending from the top of the pea gravel bed to the base of the underlying sand media.</p>
Dispersal system toe membranes and toe areas to property lines	<p>At north end of bed area install vertical membrane to restrict flow to north, directing flow to the west downslope of the beds. Membrane to be pre approved, insert membrane minimum 60 cm into native soil below base of sand media and extend membrane up to top of pea gravel bed. Laterally, extend membrane minimum 2 m beyond edges of pea gravel bed.</p> <p>On side away from bed the membrane is to be supported by pre approved clean fill of lower permeability, which is capable of maintaining a 1v:2h slope, where necessary a low rock enclosure may be pre approved at the toe of this fill to ensure toe areas are maintained inside the property line. If the fill material contains rock or sharp gravel the membrane must be capable of maintaining integrity with this material place, or must be protected by pre approved non woven geotextile.</p>
Distribution bed air laterals	<p>Air laterals are to be pre installed in case aeration of the bed is necessary at a later date, this is to manage risk associated with the bed width being over 3 m.</p> <p>This is to be 4" Big O piping (perforated), installed in the base of the pea gravel bed, with the base of the pipe resting on the sand media. Install with 5 runs for the length of each zone, spaced mid way between effluent laterals. Each end of the pipes manifolded to 4" PVC CSA solid solvent weld sewer manifold with 4" PVC sewer solid pipe riser at each end from center of manifold, riser at one end of zone to 120 cm above final grade, painted black, and to 75 cm at other end, left white, both completed with candy cane formed with two 90 deg. elbows and a grate insert.</p> <p>To allow for future active aeration of the bed, install electrical supply to control panel adequate to power a 0.5 HP 120V blower (dedicated 15 A circuit) to each zone from the tank area.</p>
Forest cover and protection of soils	<p>Fence dispersal area and 7.5 m around prior to commencement of site development. Do not cut soils or remove or disturb vegetation in this area, and do not allow machine access or travel in the area. Do not store construction materials in the area.</p> <p>During construction, follow instructions of design engineer to reduce impact on soils and vegetation and retain trees where practical. Plant new trees after completion. Where necessary, install pea gravel tree wells around tree trunks which will be buried in sand media or other fill, with pea gravel at 60 cm around trunks. Maintenance of forest canopy cover is critical to system performance.</p> <p>Deactivate and remediate soils in old access roads under the direction of the design engineer where these fall within the dispersal or receiving areas.</p> <p>After completion of beds and cover soil, establish grass cover vegetation as rapidly as practical, biodegradable erosion control matting is to be used in the interim to protect soils.</p>
Basal/VS observation standpipes and level logger	<p>4" PVC Sewer pipe installed as shown on the plan section. One per bed at upper edge of bed near bed centerline. Side slot pipe from near base to approx. 10 cm above base of sand media using a hand saw. Backfill around the pipe with pea gravel to 10 cm above the uppermost side slot. Ensure sand media is packed around pipe during backfill and media placement.</p> <p>Extend pipe to 10 cm below final grade, terminate with threaded cleanout and plug. Drill 1/8" diameter hole in base of cleanout fitting to vent pipe. Cover with 10" diameter valve box, with pea gravel base in valve box.</p> <p>Note that the Bed 4 VS observation standpipe is to be installed to greater depth than for the other beds and is to have installed a datalogging level sensor, to be pre approved or INW PT2X with 8ft. vent and cable.</p>
Primary monitoring provisions	<p>Monitor water table observation standpipes to measure wet season seasonal water table level below dispersal bed lower edge, to provide assurance of maintenance of VS in excess of 70 cm below the infiltrative surface during normal winter conditions and minimum 40 cm at all times.</p> <p>This will include the specification of continuous monitoring through the use of the datalogging level sensor in the Bed 4 VS observation standpipe.</p>



REFERENCES

The following documents were the principal sources of reference for standard practice in this design.

The BC SEWERAGE SYSTEM STANDARD PRACTICE MANUAL Version 3, September 2014, Ian Ralston, Michael Payne for Ministry of Health. And supporting rationale documentation and calculations (on file).

The BC SEWERAGE SYSTEM STANDARD PRACTICE MANUAL Version 2, 21st September 2007, Issued By: Ministry of Health, Population Health and Wellness Health Protection.

APEGBC Professional Practice Guidelines - Onsite Sewerage Systems, V12 January 2013

Laak, R.H. 1986. Wastewater engineering design for unsewered areas, Technomic

Design Guidance for Large Subsurface Wastewater Treatment Systems (LSTS), Minnesota Pollution Control Agency, Version: 03-08-2005

Further references for performance design of custom VS, HLLR/system contour length and HS on file.

STATEMENT OF GENERAL CONDITIONS

Scope of this Report

This review report satisfies only those objectives stated in the Introduction. TRAX Developments Ltd. (TRAX) has not conducted a Hydrogeology Study or Environmental Impact Assessment.

Use of this Report

This TRAX Developments Ltd. (TRAX) report pertains only to a specific project. If the project is modified, then our client will allow us to confirm that the report is still valid. We prepared this report only for the benefit of our Client and those agencies authorized by law to regulate our Client's activities. No others may use any part of this report without our written consent. To understand the content of this report, the reader must refer to the entire, signed report. We cannot be responsible for the consequences of anyone using only a part of the report, or referring only to a draft report. This report reflects our best judgement based on information available at the time. Any use of this report, or reliance on this report, by a third party is the responsibility of that third party. We accept no responsibility for damages, if any, suffered by a third party as a result of decisions made or actions taken based on this report.

Reliance on Provided Information

TRAX has relied on the accuracy and completeness of information provided by its client and by other professionals. We are not responsible for any deficiency in this document that results from deficiency in this information.

Logs of Test Holes and Subsurface Interpretations

Ground and ground water conditions always vary across a site and vary with time. Test hole and well logs show subsurface conditions only at the locations of the test hole or well.

Descriptions of Geological Materials and Water Wells

This report includes descriptions of natural geological materials, including soil, rock, and ground water. TRAX based these descriptions on observations at the time of the study (site evaluation).

Unless otherwise noted, we based the report's conclusions and recommendations on these observed conditions. Construction activities on the site or adjacent sites may change or alter these geological materials.

Changed Conditions

Conditions encountered by others at this site may differ significantly from what we encountered, either due to natural variability of subsurface conditions or construction activities. Our client will inform us about any such changes, and will give us an opportunity to review our recommendations. Recognizing changed soil and rock conditions, or changed well conditions, requires experience. Therefore, during construction or remediation, a qualified professional should be employed to visit the site with sufficient frequency to detect if conditions have changed significantly.

Recommendations

We recommend that our client engage TRAX to review all design drawings and constructed works that are based on our conclusions and recommendations.

Declaration of Interest

Ian Ralston, in a personal capacity, is a manufacturer's representative for Geoflow Inc. in BC. TRAX undertakes to ensure that no bias toward this equipment manufacturer will be shown during design and specification.


Risks and Liability

TRAX and Ian Ralston carry insurance for errors and omissions in the amount of \$1M. In all cases the liability of TRAX and/or Ian Ralston is limited to the fees charged. By accepting and using this report the client acknowledges that they understand the insurance carried by TRAX and Ian Ralston and accepts that TRAX and Ian Ralston's liability are limited in this way.

Engineering Limited License scope

Ian Ralston holds a License from EGBC to practice engineering within the following scope of practice:


Civil Engineering. Limited to: Design, construction and maintenance of sewage systems, including site and soil evaluations for these systems. Systems of 22.7 cubic meters per day or less.



JUN 09 2021

This filing Does Not Constitute
Approval for Further Subdivision

Schedule 1 - MHP00001 - Sewage Disposal Island Health - TRAX Developments Ltd. June 9 2021 (22 pages)



9090 Trans Canada Highway,
Chemainus. Phase 1 sewerage
system (PID 009-885-200)
Keyplan showing site layout with
proposed Phase 1 modular homes.

Drawn by IPR Trax Developments Ltd. Based
survey plan and approximate field measurements.
Contours (1m) from LIDAR.


4 June 2021 R0


NOTES

Layout shown is schematic and does not show all details of proposed site use. Layout of dispersal areas and tanks is to be confirmed on site at time of construction. See specifications for vegetation and soil protection requirements for dispersal area and area surrounding.

This design is for a sewerage system serving 20 modular homes in Phase 1 of a proposed phased development of the site only. This key plan shows preliminary layout of lot lines in other phases, which may be altered over time prior to construction of those phases. Future phases will be served by other, completely separate, sewerage systems which will be designed and filed at the time of development of those phases and constructed under those separate filings.

Refer to design notes and specifications (R0). STEP main and STEP connection valves to be completed as part of the civil engineering of the project, with coordination with this design. STEP tanks are shown schematically, location to be confirmed in coordination with civil engineers (including with consideration of separation to modular home pads for structural requirements). Refer to civil drawings. For details of site development plans, including proposed site grading and general location of site and legal plans, refer to civil, geotechnical and other plans and reports.





THIS FILING DOES NOT CONSTITUTE APPROVAL FOR FURTHER SUBDIVISION
 JUN 09 2021
 This filing Does Not Constitute Approval for Further Subdivision

NOTES

See specifications, R0.

Section schematic and preliminary, confirm section and layout at installation with the design engineer. Design engineer to be retained to confirm layout and inspect bed layout and scanned soils prior to sand installation. All aggregate, sand and cover soil materials to be pre-approved by the design engineer.

Where machinery must travel on bed and receiving area use only pre-approved tracked machines and restrict travel to pre-approved locations, during periods where soil moisture is suitable to reduce risk of soil damage.

The grass on the beds and toe areas is to be kept mowed or cut during system operation. To facilitate this it is recommended that the toe areas be flattened, where practical, to 1.3 or 1.4 to allow mowing. The toe areas where beds are placed close to property lines will need to be maintained at the maximum allowable slope, requiring vegetation management with a trimmer.

9090 Trans Canada Highway,
 Chemainus, Phase 1 sewerage
 system (PID 009-885-200)
 Sewerage system typical section
 showing sand media beds.




UPSLOPE SIDE

Schematic only. Shows typical single zone within a bed. Confirm forcemain size, zone lengths, orifice number with design engineer at final layout. Do not scale or count from this schematic; refer to specifications.

[illegible]

ISLAND HEALTH
FILING ACCEPTED

JUN 09 2021

This Filing Does Not Constitute
Approval for Further SubdivisionSCHEMATIC SECTION OF BIOFILTER MEDIA BED (TYP.)
VERTICAL PROPORTION 1:1 (N.T.S.)

C

NOTES AND SPECIFICATIONS:

Section schematic, confirm section and layout at installation with the design engineer.

Place biofilter above top of lid elevation of highest tank, and feed with air with passive vents (2 of, see specifications).

Biofilter media is to consist of a pre-approved mix of 19 mm plus clean wood chips or shreds with mature, stable, low odor compost at 30 to 50% compost to 70 to 50% wood chips mix (by dry weight). Ground oyster shell or dolomite prills are to be added to this mix at 5% by weight. The contractor is to provide test results showing final void ratio as settled, with a target of 50% and minimum 40%.

All aggregate and media as well as any proposed substitutions to be pre-approved by the design engineer based on submissions from the contractor. System may be installed partially above grade, with media placed above the ground surface and the chamber installed below grade, in that case ensure that media depth above the pea gravel is minimum 35 cm in all directions and scarify media to any native soil below to reduce risk of short circuiting. Ensure bed is placed in a location with permeable soil below the bed to avoid risk of saturation during rainfall, with minimum vertical separation of 60 cm to SHWT or flow restrictive layer in pre approved native soil or sand media fill. Install with base of bed level. Divert stormwater flows away from bed area.

Dripline is intended to maintain moist conditions in biofilter media. The dripline may be installed as a single line, looped at bed ends. Follow manufacturer guidelines for installation, and particularly, provide an air valve to protect the dripline from aspiration of particles during depressurization. Dosing may be controlled by any standard single zone irrigation controller, or as part of an existing irrigation zone, and the operator is to adjust dosing to maintain biofilter media at a suitable moisture content as directed by the design engineer.

The operator is to control weed growth on the biofilter and rodent control may be necessary to prevent burrowing animals forming channels in the filter or entering the chambers. If burrowing animals are thought to be a potential issue, place chambers on $\frac{1}{2}$ " stainless steel mesh attached to base of chambers with plastic strips and stainless steel screws.

The locations of the biofilter trench edges are to be marked with permanent labeled steel posts. Prevent traffic on bed with suitable barrier.

The contractor is to provide shop drawings for pre approval showing details of ducting, ports etc. and including media test results for pre approval.

9090 Trans Canada Highway,
Cheminus, Phase 1 sewerage
system (PID 009-885-200)
Sewerage system vent biofilter

This filing Does Not Constitute
Approval for Further Subdivision



1.25" MIP X 1" FIP BUSHING, STAINLESS

1" MIP X SLIP UNION, LASCO SCH 80 PVC WITH ORIFICE PLATE.

1" SCH 40 PVC SLIP 90

1" SCH 40 PVC PIPE TO BASE OF TANK, WITH TEE AT BASE TO SUPPORT DISCHARGE ASSY AND DIFFUSE FLOW

1.25" MIP X FEMALE CAMLOCK, STAINLESS

1.25" MIP X BARB STAINLESS STEEL WITH ALL SS HOSE CLAMPS (2 OF)

1.25" FIP BALL VALVE, STAINLESS

1.25" SPRING CHECK, STAINLESS

1.25" TEE, STAINLESS

PUMP, INSTALL VERTICALLY ON BASE OF TANK.

1.25" SIDE PIPE TO STEP COLLECTOR (SEE CIVIL DRAWINGS)

1.25" HDPE EXITS PUMP CHAMBER THROUGH RISER. SEAL WITH GROMMET AND SEALANT

1.25" GREENLINE G242-125 HOSE

1.25" MIP X BARB STAINLESS WITH 2 OF ALL STAINLESS T-BOLT CLAMPS

9090 Trans Canada Highway,
Chemainus, Phase 1 sewerage
system (PID 009-885-200)
Sewerage system STEP effluent
pump discharge assembly.

Barb fittings must be sized correctly for SDR8 (pump drop) pipe, warm pipe prior to clamping over barb. Use barb gbs if necessary to align HDPE pipe on tank with SM sheet if cover is less than 30 cm.

Drill discharge orifice in pre approved HDPE disc to fit union. Confirm discharge orifice size with design engineer, default 3/16". Lightly coat side of disc on nut side of union with silicone sealant to retain disc during disassembly.

Externally weighted floats. See specifications for settings.

TRAX Developments Ltd.

Pump Float Setting Worksheet 9090 TCH Ph1, 2 of 5100IG Dans		Imperial Units Height above 5100 chamber floor, see note		Ht to float Above 5100 chamber floor	
V = 0.007807711 For two tanks		Inches LID		Inches	
107 inches		107.0			
Base of lid	98 Actual height from input (4" boot at inlet level)	98.5			
Overflow	50 % of DDF Alarm reserve volume (ARV) = 2919.101012 Alarm reserve height = ARV x V 2919.101 X 0.007807711 = 22.8	22.8			
Alarm	67 % of DDF Reserve volume 2 (RV2) = 3911.595356 Reserve height = RV2 x V 3911.5954 X 0.007807711 = 30.5	30.5		73.00	
Lag timer	75 % of DDF Reserve volume (RV) = 4378.651518 Reserve height = RV x V 4378.6515 X 0.007807711 = 34.2	34.2		42.20	
Timer allow	Minimum 1" c-sensor setting	11.0		8.00	
0.2 inches Float tether length 3.5 inches (3.5 in min)	Dose volume (DV) = 21 Pump range = DV x V 21 X 0.007807711 = 0.2	0.2		C sensor setting	
Low level float	Drainback, If NO: DB = 0, If YES Drainback = DB x V 0 X 0.007807711 = 0.0	0.0		C sensor setting	
Tank dimensions: 165 in Long 98 in Wide 118 in High	Pump cooling height = 10.0	10.0		7.00	
	Pump spacer height = 0.0	0.0		C sensor setting	
	Base of 24" vault	0.0		6.00	
				Float	
				3.00	
				C sensor collar	
Draw down for design flow	0.687	Inches per min	Flow rate	88.0 usgpm	Time 0.239 mins
Check volume for residual height	Dose volume 21.0 usgal	1 pump per zone	15	Secs	Standard timer
	Doses per day 140	280	10:00	Mins Sec	Standard timer off
Residual ht to inv. Outlet	-0.5 Inches				
Represents volume	-66.52 Gallons				
<p>Notes:</p> <p>V based on two tanks. Manifold at base with 4" Sch 40 PVC and at inlet risers with 2" Sch 40 PVC pipe. Install with bases at same level. Inlet to tanks from final septic tank outlet. Inlet and Outlet boots are 4" boot installed at normal inlet height. Use C-sensor level control with SJE Rhombus EZI panel (or as necessary for custom panel). Strict timed dosing. Override timer to result in discharge of DDF, 280 doses per day (28 per each of 10 zones). Provide redundant off and high level floats, SJE Rhombus Sensor Float, externally weighted.</p> <p>C-sensor collar set at 3" below elevation of internal base of 5100 tanks. Check setting to ensure C-sensor reads 1" when water is 4" deep in 5100 IG tanks.</p> <p>Note that settings are based on invert of lower manifold pipe being at internal base of 5100 IG tanks.</p> <p>Install tanks to allow surcharge to preceding septic tanks for additional alarm reserve volume. Tanks vented from riser, connect both tanks to vent system to allow surcharge to lid.</p>					
<p>ISLAND HEALTH FILING ACCEPTED</p> <p>JUN 09 2021</p> <p>This filing Does Not Constitute Approval for Further Subdivision</p>					

6/4/2021

9090TCH_Phase1_floatsetting_2 of 5000gal_NoVault_R0.xls


TRAX DEVELOPMENTS LTD.

SEWERAGE SYSTEM SITE AND SOIL NOTES, RATIONALE NOTES




Design	9090 TCH Phase 1	Friday, June 4, 2021
Revision	Rev. 0	Client: Core Group Civil Consultants
Notes	<p>Test pits were excavated by 20 T class excavator in February 2021, and logged by Ian Ralston and Henry VanHell and permeability tests were made by Henry VanHell ROWP, with site visits, earlier hand auger testing and review by Ian Ralston. Original logs and photographs on file. Evaluation also considered geotechnical report by Geopacific with test pit information and permeability testing (on file). Further evaluation of SHWT was based on observation of the cutbank along the Trans Canada Highway for the NE part of the site, and of existing groundwater monitoring standpipes.</p>	

Permeability	<p>6 tests have been made using a constant head borehole permeameter at 40 cm BGS, by Henry VanHell, February 2021. Calculations on file..Kfs Median 1320 mm/day and range of 1000 to 1700 mm/day.</p> <p>The geotechnical report included the results of two infiltration tests in soils at 1.6 and 1.8 m BGS. The test in the till layer characteristic of till below soils in areas identified as suitable for dispersal at a depth of 1.8 m BGS showed a long term infiltration rate of 166 mm/hr, and the test at 1.6 m BGS in lower permeability Silty Clay Loam or Clay Loam soil showed a rate of 8.4 mm/hour. For dispersal area design this supports the interpretation that the till layers found below the usable soil depth in TP3, 4, 5, and geotechnical pits 3, 4, 5 and 13 are likely to show significant permeability, despite being classified as a limiting layer due to their cemented consistency, reducing risk of water table mounding in soils below dispersal areas.</p>
Summary of soils for pits representing the planned Phase 1 sewerage system dispersal area	<p>TP3: (outside of area selected for Phase 1 dispersal system)</p> <p>L1- 0 to 15 cm Black, Sandy Loam SABK/3, VFR, Roots Fine to Medium, Many. Coarse Fragments 3% gravel</p> <p>L2- 15 to 80 cm Brown, Sandy Loam ABK/3, VFR, Roots Fine to Medium, Few. Coarse Fragments 3% gravel and cobbles</p> <p>L3- 80 to 110 cm Tan, Sandy Loam (Till) Pseudo Platy/3, M Cemented, Roots Fine, Few. Coarse Fragments 10% gravel and cobbles</p> <p>Base of pit on weathered Till. No SHWT observed. No mottling observed.</p> <p>Some stones in all layers.</p> <p>No moisture or seepage observed. Interpreted SHWT >110 cm. L3 considered a limiting layer by the SPM, but expected to show significant permeability (see above) and shows root penetration.</p> <p>TP4:</p> <p>L1- 0 to 15 cm Black, Sandy Loam and Loam SABK/3, VFR, Roots Fine, Many. Coarse Fragments 3% gravel</p> <p>L2- 15 to 60 cm Brown, Sandy Loam ABK/3, VFR, Roots Fine to Medium, Many. Coarse Fragments 3% gravel and cobbles</p> <p>L3- 60 to 145 cm Tan, Sandy Loam (Till) Pseudo Platy/3, EW Cemented, Roots Fine, Few. Coarse Fragments 10% gravel and cobbles</p> <p>Base of pit on weathered Till. No SHWT observed. Some small patches of mottling observed in L3, but no evidence of perched water tables despite wet weather antecedent.</p> <p>No moisture or seepage observed. Interpreted SHWT >145 cm. L3 not a restrictive layer (EWC consistence).</p> <p>TP5:</p> <p>L1- 0 to 15 cm Black, Sandy Loam and Loam SABK/3, VFR, Roots Fine, Common. Coarse Fragments 3% gravel</p> <p>L2- 15 to 50 cm Brown, Sandy Loam ABK/3, VFR, Roots Fine to Medium, Common. Coarse Fragments 3% gravel and cobbles</p> <p>L3- 50 to 90 cm Tan, Sandy Loam ABK/3, VFR, Roots Fine to Medium, Common. Coarse Fragments 3% gravel and cobbles</p> <p>L4- 90 to 140 cm Grey, Sandy Loam (Till) Pseudo Platy/3, M Cemented, Roots Fine, Few. Coarse Fragments 10% gravel and cobbles</p> <p>Base of pit on weathered Till. No SHWT observed. No mottling observed.</p> <p>No moisture or seepage observed. Interpreted SHWT >140 cm. L4 not a restrictive layer (EWC consistence).</p> <p>Interpretation of SHWT depth confirmed by old monitoring well in potential western receiving area, showing ~150 cm to water table in winter conditions, and no evidence of water table on cut bank to TCH east of potential dispersal area (despite Till exposure) and no water in road ditch along the NE part of the site.</p> <p>Geotechnical pit #05 in the relevant area showed "very dense" sand with some silt at 1.2 m and no seepage to depth of pit at 1.6 m, similar conditions.</p> <p>Soil type for HLR selection for sand media basal area Sandy Loam, Favorable structure and consistence category. For HLLR selection same soil but with consideration of deep percolation to Till layer. For conservative contour loading and VS design utilize 120 cm nominal soil depth.</p>
Summary of site information	<p>Refer to geotechnical report for general details of site.</p> <p>The proposed dispersal area slopes at approximately 20% from a ridgeline crest at the east property line toward the west and NWW. The area is treed in young second growth Douglas fir forest.</p>



Horizontal setback triggers and risk	<p>No wells are reported within 30 m of the proposed dispersal area, and the location is serviced with municipal water.</p> <p>Key critical setback trigger is risk of breakout toward the road allowance (to the east of the proposed system). While evaluation did not show any rainfall generated water flow from the curb to the highway there is a risk that percolate may surface in this area.</p> <p>The closest expected point of breakout to the system would be 3m to the east from dispersal bed, based on consideration of depth to Till layers in the soil. Breakout to the east is seen to be lower risk in terms of human contact than to the west (where residences will be sited), so breakout to the west is to be maintained at SPM standard separation. There may be some risk of breakout to the Henry Road unused road allowance to the north of the site, which is side slope to the proposed dispersal beds. Risk is considered the same or lower for contact compared to the highway road cut, which is controlling.</p> <p>Custom, performance based, horizontal separation to potential surface breakout has been developed based on custom HLR and VS rationale, on file, following EGBC guidelines, to manage risk to health and avoid causing a health hazard. Further risk management will include the use of key trenches to improve deep infiltration of percolate, and placement of dispersal beds to ensure flows to the west of the system for over 50% of the percolate.</p> <p>Note that layout of the system is to be made to maximize HS to potential breakout.</p> <p>Given that the road ditch to the east of the system does not show evidence of surface flow during wet season conditions this ditch is considered ephemeral and not a setback boundary for design.</p> <p>In order to improve system performance (through reducing contour loading rate and to place system in most favorable topographic location and in most favorable soils) non critical setback to property lines (existing or proposed) may be reduced. To manage risk any lines are to be laid out by survey and setback maintained at 1 m minimum.</p>
Site and project specific horizontal separation summary	<p>To property lines, 1 m.</p> <p>To potential surface breakout, 3 m (reduced from 7.5 m) minimum, for breakout toward east or north road allowances only. 7.5 m to be maintained on west side of system.</p>
Selected location	<p>Location along east property line is chosen to:</p> <ul style="list-style-type: none"> - Use area of favorable, undisturbed native soils - Take advantage of favorable topography, including alignment with possibility of flows to both sides of a ridge, and ridge alignment with reduced risk of run on from other areas. - Allow installation approximately on contour and maximize length on contour. - Allow for current and potential future site development plans by using an area not designated for other uses. - Address landscaping objectives by backing against existing roadway and providing a vegetated buffer
Rationale notes, custom, performance based design	<p>Given the size of the system and the restricted area available for dispersal system construction (based on site characteristics and proposed development—both current and future), and the need to use the most favorable available area resulting in reduced setback to breakout (custom HS), the design has been based on custom, performance based rationale per EGBC guidelines and following the approach used for development of BC SPM standards, together with the performance objectives of the BC SPM and BC Water Quality Objectives.</p> <p>This approach consists of setting performance objectives for water (percolate) flowing from the dispersal system to the receiving area. In this case, objectives have been set for water flowing to potential breakout to surface. Dispersal system design has been based on the need to achieve these objectives.</p> <p>The median objectives established for this project for percolate surfacing within 7.5 m of the dispersal beds are based on SPM performance objectives, EGBC guidelines for surface breakout and with safety factor intended to support the use of VS monitoring as a surrogate for pathogen attenuation performance, and are as follows:</p> <ul style="list-style-type: none"> •Acute pathogen Indicator objective, fecal coliforms median <200 CFU/100 mL •Chronic pathogen Indicator objective, fecal coliforms median 0.02 CFU/100 mL or less <p>To support improved pathogen attenuation a custom VS has been developed, based on the use of micro timed dosing and reduced HLR coupled with the use of sand media and a greater VS than that required by SPM standards. During operation, monitoring of the dispersal system will utilize VS as a surrogate for system performance.</p> <p>Rationale retained on file, including custom, performance based, contour loading, water table mounding calculations, custom analysis of Vertical Separation, supported by modeling of performance in the design VS, and custom HS.</p>






RECORD OF SEWERAGE SYSTEM

		Filing # (OFFICE USE ONLY)			
		DC23/072			
1. Property Information	<input checked="" type="checkbox"/> New Construction		<input type="checkbox"/> Alteration		<input type="checkbox"/> Repair
					<input type="checkbox"/> Amendment – Original Filing #
	Tax Assessment Roll # PID provided.				PID # 009-885-200
	Legal Description (Plan, Lot, District Lot, Block Numbers) THE EAST 60 ACRES OF SECTION 10, RANGE 5, CHEMAINUS DISTRICT, EXCEPT 16.5 FOOT STRIP ALONG AND AJJOINING				THE NORTH AND EAST BOUNDARIES THEREOF, RESERVED FOR ROAD PURPOSES, EXCEPT PARTS IN PLANS 11489, 26194 AND VIP68870
		Street (Civic) Address or General Location 9090 Trans Canada Highway Phase 2		City Chemainus	
2. Owner Information	Name of Legal Owner 1230226 B.C. LTD			Mailing Address C/O TRAX Developments Ltd. Box 9-6	
	Phone 250-246-4774		City Thetis Island		Prov BC
					Postal Code V0R2Y0
3. Authorized Person Information	Name of Authorized Person Ian Ralston			Mailing Address Box 9-6	
	Phone 250-246-4774		City Thetis Island		Prov BC
					Postal Code V0R2Y0
	Registration # 158292		Email onsite@traxdev.com		
4. Structure Information	Sewerage System Will Serve:				
	<input type="checkbox"/> Single Family Dwelling <input type="checkbox"/> Other Structure (specify) _____ <input checked="" type="checkbox"/> Other Dwelling (specify) <u>20 Mobile homes</u>				
	The sewerage system is designed for an estimated minimum daily domestic sewage flow of (check one) <input type="checkbox"/> Less than or equal to 9,100 litres <input checked="" type="checkbox"/> More than 9,100 litres but less than 22,700 litres				
5. Site Information	Depth of native soil to seasonal high water table or restrictive layer (cm) 70 cm, see specs		Information respecting the type, depth and porosity of the soil (sand media) is attached <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
	GPS Location of System (decimal degrees) Latitude <u>N 48.89932814999155</u> Longitude <u>W 123.71830026256758</u>				
	Horizontal Accuracy (m) <u>10</u> <input checked="" type="checkbox"/> Recreational GPS <input type="checkbox"/> Differential GPS				
6. Drinking Water Protection	Will the sewerage system be located less than 30 m from a water well? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No				
	If yes, attach a professional's report and specify the intended distance _____ (m)				
	Distance of proposed sewerage system to the closest body of surface water <u>>30 m to permanent fresh water</u> (m)				
7. System Information	Sewerage treatment method <input checked="" type="checkbox"/> Type 1 <input type="checkbox"/> Type 2 <input type="checkbox"/> Type 3				
8. Legal or Regulatory Considerations	<input checked="" type="checkbox"/> Construction of the proposed sewerage system will not conflict with legal instruments registered on the property. See specifications		Is this filing submitted as the result of an order from the Health Authority? <input type="checkbox"/> Yes (attach a copy of the order) <input checked="" type="checkbox"/> No		
9. Plot Plan and Specifications	Plot Plan (to scale) and specifications are attached <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No				
	<input checked="" type="checkbox"/> The plans and specifications are consistent with Standard Practice Source of Standard Practice: <input checked="" type="checkbox"/> Ministry of Health Standard Practice Manual <input checked="" type="checkbox"/> Other See design notes				
10. Authorized Person's Signature	Signature 		OFFICE USE ONLY		
	Date 30 April 2023		Filing Accepted Date <u>May 1/23</u>		
			Receipt Number <u>#200.00</u> <u>#099381</u>		

ISLAND HEALTH
SCHEDULE 2

MAY 01 2023

This filing Does Not Constitute
Approval for Further Subdivision



I am the Author
Association of Professional
Engineers and Geoscientists
of the Province of
British Columbia
PRALATON
ENGINEERING
2023-04-30
1003548
158292

9090 Trans Canada Highway,
Chemainus. Phase 2 sewerage
system (PID 009-885-200)
Keyplan showing site layout with
proposed Phase 2 modular homes.

Drawn by IPR Trax Developments Ltd. Based
survey plan, client plans, MNC mapping and
approximate field measurements. Contours (1m)
from LIDAR.


29 April 2023 R0


NOTES:

Layout shown is schematic and does not show all details of proposed site use. Layout of dispersal areas and tanks is to be confirmed on site at time of construction. See specifications for vegetation and soil protection requirements for dispersal area and area surrounding.

This design is for a sewerage system serving up to 20 modular homes in Phase 2 of a proposed phased development of the site only. This key plan shows preliminary layout of lot lines in other phases, which may be altered over time prior to construction of those phases. Phase 1 and future phases will be served by other, completely separate, sewerage systems which will be designed and filed at the time of development of those phases and constructed under those separate filings.


Refer to design notes and specifications (R0). STEP main and STEP connection valves to be completed as part of the civil engineering of the project, with coordination with this design through shop drawing review. STEP tanks are shown schematically, location to be confirmed in coordination with civil engineers (including with consideration of separation to modular home pads for structural requirements). Refer to civil drawings. For details of site development plans, including proposed site grading and general location of site and legal plans, refer to civil, geotechnical and other plans and reports. TRAX's scope does not include structural or geotechnical engineering.






LEGAL DESCRIPTION:
THE EAST 60 ACRES OF SECTION 10, RANGE 5,
CHIMANUS DISTRICT,
THE NORTH AND EAST BOUNDARIES, EXCEPT PARTS IN
RESERVED FOR ROAD PURPOSES, EXCEPT PARTS IN
P.O. No. 201-201-201

CIMC ADDRESS:
8000 ISLAND HIGHWAY, CHIMANUS, BC



DISTRICT OF NORTH COWICHAN	
DESIGNED BY	DB
DRAWN BY	DB
DATE	11/10/20
APPROVED BY	ON
DATE	DEC 10, 2021
MORGAN MAPLES	
LOT BUILD OUT	
PHASING PLAN	
8000 ISLAND HIGHWAY, CHIMANUS, BC	
FILE NO.	201-201-201
CONSULTANTS	DB
DWG NO.	11/10/20
CITY	CHIMANUS
DOC NO.	CHIMANUS
SHEET	16 OF 16

CoreGroup
CONSULTANTS
LAND DEVELOPMENT SERVICES
3750 BRIDGEWAY, SUITE 100
VICTORIA, BC V8N 2G5
Tel: (604) 299 0205 Fax: (604) 299 0629
Printed To: Practice No. 100017 (BC)





CHECK BEFORE YOU DIG
INFORMATION ON EXISTING UTILITIES MAY NOT BE COMPLETE. FOR
YOUR PROTECTION, WE HAVE ADVISED YOU OF THE LOCATION OF
ALL KNOWN UTILITIES. YOU ARE RESPONSIBLE FOR VERIFYING THE
EXISTENCE, LOCATION OF ALL EXISTING UTILITIES AND ADVISE THE
EMPLOYER OF ANY POTENTIAL CONFLICTS. THIS DRAWING IS TO BE
USED FOR INFORMATIONAL PURPOSES ONLY. IT DOES NOT
GUARANTEE THE LOCATION, DEPTH, OR TYPE OF UTILITIES.
LOCATION OF THESE UTILITIES SHALL BE DETERMINED ON SITE.

REV	DATE	BY	CHKD	DESCRIPTION
1	2023/11/10	DB	ON	DEVELOPMENT PERMIT SUBMISSION
0	2023/03/20	DB	ON	DEVELOPMENT PERMIT SUBMISSION
REVISED (DATE BY CHKD) (REV) (CHKD)				

REVISIONS:
1. CLEARANCE AND ERECTION (FROM TABLE)
2. MARKING (FROM TABLE) (FROM TABLE) (FROM TABLE)
3. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
4. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
5. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
6. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
7. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
8. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
9. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
10. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
11. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
12. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
13. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
14. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
15. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
16. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
17. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
18. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
19. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
20. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
21. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
22. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
23. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
24. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
25. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
26. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
27. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
28. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
29. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
30. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
31. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
32. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
33. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
34. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
35. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
36. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
37. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
38. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
39. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
40. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
41. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
42. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
43. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
44. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
45. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
46. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
47. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
48. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
49. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
50. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
51. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
52. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
53. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
54. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
55. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
56. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
57. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
58. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
59. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
60. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
61. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
62. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
63. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
64. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
65. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
66. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
67. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
68. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
69. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
70. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
71. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
72. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
73. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
74. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
75. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
76. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
77. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
78. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
79. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
80. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
81. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
82. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
83. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
84. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
85. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
86. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
87. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
88. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
89. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
90. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
91. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
92. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
93. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
94. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
95. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
96. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
97. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
98. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
99. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)
100. CHIMANUS (FROM TABLE) (FROM TABLE) (FROM TABLE)


Schedule 3 - MHP00001 - Landscaping Plan and Security - PMG Landscape Architects May 16, 2022 (8 pages)



PLANT SCHEDULE			
NO.	DEF.	SCIENTIFIC NAME	COMMON NAME
1	1	SPERMATOPHYTES	DAWSON'S BARBERRY, YELLOW ORANGE
2	2	CONIFERAE	CALIFORNIA LEAD
3	3	CHAMAEPSYDAS	COMPACT HENRY CYPRESS
4	4	HOLCIDIACEAE	OSGANDER
5	5	MAHONIA	LONGLEAF MAHONIA
6	6	ROSA	ROSE
7	7	ROSA	ROSE
8	8	ROSA	ROSE
9	9	ROSA	ROSE
10	10	ROSA	ROSE
11	11	ROSA	ROSE
12	12	ROSA	ROSE
13	13	ROSA	ROSE
14	14	ROSA	ROSE
15	15	ROSA	ROSE
16	16	ROSA	ROSE
17	17	ROSA	ROSE
18	18	ROSA	ROSE
19	19	ROSA	ROSE
20	20	ROSA	ROSE
21	21	ROSA	ROSE
22	22	ROSA	ROSE
23	23	ROSA	ROSE
24	24	ROSA	ROSE
25	25	ROSA	ROSE
26	26	ROSA	ROSE
27	27	ROSA	ROSE
28	28	ROSA	ROSE
29	29	ROSA	ROSE
30	30	ROSA	ROSE
31	31	ROSA	ROSE
32	32	ROSA	ROSE
33	33	ROSA	ROSE
34	34	ROSA	ROSE
35	35	ROSA	ROSE
36	36	ROSA	ROSE
37	37	ROSA	ROSE
38	38	ROSA	ROSE
39	39	ROSA	ROSE
40	40	ROSA	ROSE
41	41	ROSA	ROSE
42	42	ROSA	ROSE
43	43	ROSA	ROSE
44	44	ROSA	ROSE
45	45	ROSA	ROSE
46	46	ROSA	ROSE
47	47	ROSA	ROSE
48	48	ROSA	ROSE
49	49	ROSA	ROSE
50	50	ROSA	ROSE
51	51	ROSA	ROSE
52	52	ROSA	ROSE
53	53	ROSA	ROSE
54	54	ROSA	ROSE
55	55	ROSA	ROSE
56	56	ROSA	ROSE
57	57	ROSA	ROSE
58	58	ROSA	ROSE
59	59	ROSA	ROSE
60	60	ROSA	ROSE
61	61	ROSA	ROSE
62	62	ROSA	ROSE
63	63	ROSA	ROSE
64	64	ROSA	ROSE
65	65	ROSA	ROSE
66	66	ROSA	ROSE
67	67	ROSA	ROSE
68	68	ROSA	ROSE
69	69	ROSA	ROSE
70	70	ROSA	ROSE
71	71	ROSA	ROSE
72	72	ROSA	ROSE
73	73	ROSA	ROSE
74	74	ROSA	ROSE
75	75	ROSA	ROSE
76	76	ROSA	ROSE
77	77	ROSA	ROSE
78	78	ROSA	ROSE
79	79	ROSA	ROSE
80	80	ROSA	ROSE
81	81	ROSA	ROSE
82	82	ROSA	ROSE
83	83	ROSA	ROSE
84	84	ROSA	ROSE
85	85	ROSA	ROSE
86	86	ROSA	ROSE
87	87	ROSA	ROSE
88	88	ROSA	ROSE
89	89	ROSA	ROSE
90	90	ROSA	ROSE
91	91	ROSA	ROSE
92	92	ROSA	ROSE
93	93	ROSA	ROSE
94	94	ROSA	ROSE
95	95	ROSA	ROSE
96	96	ROSA	ROSE
97	97	ROSA	ROSE
98	98	ROSA	ROSE
99	99	ROSA	ROSE
100	100	ROSA	ROSE

NOTES: *PLANT SEEDS IN THIS LIST ARE SPECIFIED ACCORDING TO THE BC LANDSCAPE STANDARD AND CANADIAN LANDSCAPE STANDARD, LATEST EDITION. CONTAINER SEEDS SPECIFIED AS PER CANADA STANDARD. BOTH PLANT SEED AND CONTAINER SEEDS ARE THE MINIMUM ACCEPTABLE SEEDS. *PREFER TO SPECIFY SEEDS FOR SEEDS CONTAINER SEEDS AND OTHER PLANT MATERIAL REQUIREMENTS. *SEARCH AND REVIEW: MAKE PLANT MATERIAL AVAILABLE FOR OPTIONAL REVIEW BY LANDSCAPE ARCHITECT AT BOUNDARY OF SITE. *AREA OF SEARCH TO BE LOW, LOWER MIDDLE AND UPPER VALLEY. *SUBSTITUTION: OBTAIN WRITTEN APPROVAL FROM THE LANDSCAPE ARCHITECT PRIOR TO MAKING ANY SUBSTITUTIONS TO THE SPECIFIED MATERIAL. UNAPPROVED SUBSTITUTIONS WILL BE REJECTED. ALLOW A MINIMUM OF FIVE DAYS PRIOR TO DELIVERY FOR REQUEST TO SUBSTITUTE. SUBSTITUTIONS ARE SUBJECT TO BC LANDSCAPE STANDARD AND CANADIAN LANDSCAPE STANDARD. *DEFINITION OF CONDITIONS OF AVAILABILITY: ALL LANDSCAPE MATERIALS AND EQUIPMENT MUST MEET OR EXCEED BC LANDSCAPE STANDARD AND CANADIAN LANDSCAPE STANDARD LATEST EDITION. *ALL PLANT MATERIAL MUST BE PROVIDED FROM CERTIFIED DISEASE FREE NURSERY. *BIOLOGICAL NOT PERMITTED IN GROUNDING MEDIUM UNLESS AUTHORIZED BY LANDSCAPE ARCHITECT.

Schedule 3 - MHP00001 - Landscaping Plan and Security - PMG Landscape Architects May 16, 2022 (8 pages)



pmg
LANDSCAPE
ARCHITECTS
Suite 1100 - 1180 West 10th Street
Vancouver, British Columbia, V6C 3M8
p: 604-294-0211 f: 604-294-0222

COREGROUP CONSULTANTS


REV.	DATE	BY	DESCRIPTION
1	2022-04-11	MCV	ISSUED FOR CONSTRUCTION
2	2022-04-11	MCV	REVISION: ADD PLANTING
3	2022-04-11	MCV	REVISION: ADD PLANTING
4	2022-04-11	MCV	REVISION: ADD PLANTING
5	2022-04-11	MCV	REVISION: ADD PLANTING
6	2022-04-11	MCV	REVISION: ADD PLANTING
7	2022-04-11	MCV	REVISION: ADD PLANTING
8	2022-04-11	MCV	REVISION: ADD PLANTING
9	2022-04-11	MCV	REVISION: ADD PLANTING
10	2022-04-11	MCV	REVISION: ADD PLANTING

MORGAN MAPLES
9090 TRANS-CANADA HIGHWAY
CHEMAINUS, BC

**PLAY ENLARGEMENT
PLAN**


DATE: 22 APR 22
SCALE: 1:100
DRAWN: DO
DESIGN: DO
CHECK: MCV
PROJECT NUMBER: 22-078
OF 4

Schedule 3 - MHP00001 - Landscaping Plan and Security - PMG Landscape Architects May 16, 2022 (8 pages)




• ALL MATERIALS AND LABOUR TO MEET LATEST CILA STANDARDS.

1 TREE PLANTING DETAIL
L1 1/25



2 SPEA SPLIT RAIL FENCE WITH METAL SIGN
L1 1/25



3 1.2M HEIGHT CHAIN LINK FENCE
L1 1/25



SWING SET AND SLIDE STRUCTURE



WOODEN PARKER BENCH
WITH RECYCLED PLASTIC LUMBER
TEXTURED BLACK POWDER COAT




WOODEN PARKER TABLE
WITH RECYCLED PLASTIC LUMBER
TEXTURED BLACK POWDER COAT



WOODEN PLAY STRUCTURE WITH SLIDE



WOODEN PLAY STRUCTURE



4 HIGHWAY BUFFER SECTION (TYP)
L1 1/25

pmg
LANDSCAPE
ARCHITECTS

2000 FIVE - 1500 10th Street, Suite 100
Vancouver, British Columbia, V6C 1G8
P: 604-294-0211 | F: 604-294-0222

COREGROUP CONSULTANTS

REV.	DATE	DESCRIPTION	BY
1	2022-05-16	ISSUED FOR CONSTRUCTION	MA
2	2022-05-16	ISSUED FOR CONSTRUCTION	MA
3	2022-05-16	ISSUED FOR CONSTRUCTION	MA
4	2022-05-16	ISSUED FOR CONSTRUCTION	MA
5	2022-05-16	ISSUED FOR CONSTRUCTION	MA
6	2022-05-16	ISSUED FOR CONSTRUCTION	MA
7	2022-05-16	ISSUED FOR CONSTRUCTION	MA
8	2022-05-16	ISSUED FOR CONSTRUCTION	MA
9	2022-05-16	ISSUED FOR CONSTRUCTION	MA
10	2022-05-16	ISSUED FOR CONSTRUCTION	MA
11	2022-05-16	ISSUED FOR CONSTRUCTION	MA
12	2022-05-16	ISSUED FOR CONSTRUCTION	MA
13	2022-05-16	ISSUED FOR CONSTRUCTION	MA
14	2022-05-16	ISSUED FOR CONSTRUCTION	MA
15	2022-05-16	ISSUED FOR CONSTRUCTION	MA
16	2022-05-16	ISSUED FOR CONSTRUCTION	MA
17	2022-05-16	ISSUED FOR CONSTRUCTION	MA
18	2022-05-16	ISSUED FOR CONSTRUCTION	MA
19	2022-05-16	ISSUED FOR CONSTRUCTION	MA
20	2022-05-16	ISSUED FOR CONSTRUCTION	MA
21	2022-05-16	ISSUED FOR CONSTRUCTION	MA
22	2022-05-16	ISSUED FOR CONSTRUCTION	MA
23	2022-05-16	ISSUED FOR CONSTRUCTION	MA
24	2022-05-16	ISSUED FOR CONSTRUCTION	MA
25	2022-05-16	ISSUED FOR CONSTRUCTION	MA
26	2022-05-16	ISSUED FOR CONSTRUCTION	MA
27	2022-05-16	ISSUED FOR CONSTRUCTION	MA
28	2022-05-16	ISSUED FOR CONSTRUCTION	MA
29	2022-05-16	ISSUED FOR CONSTRUCTION	MA
30	2022-05-16	ISSUED FOR CONSTRUCTION	MA
31	2022-05-16	ISSUED FOR CONSTRUCTION	MA
32	2022-05-16	ISSUED FOR CONSTRUCTION	MA
33	2022-05-16	ISSUED FOR CONSTRUCTION	MA
34	2022-05-16	ISSUED FOR CONSTRUCTION	MA
35	2022-05-16	ISSUED FOR CONSTRUCTION	MA
36	2022-05-16	ISSUED FOR CONSTRUCTION	MA
37	2022-05-16	ISSUED FOR CONSTRUCTION	MA
38	2022-05-16	ISSUED FOR CONSTRUCTION	MA
39	2022-05-16	ISSUED FOR CONSTRUCTION	MA
40	2022-05-16	ISSUED FOR CONSTRUCTION	MA
41	2022-05-16	ISSUED FOR CONSTRUCTION	MA
42	2022-05-16	ISSUED FOR CONSTRUCTION	MA
43	2022-05-16	ISSUED FOR CONSTRUCTION	MA
44	2022-05-16	ISSUED FOR CONSTRUCTION	MA
45	2022-05-16	ISSUED FOR CONSTRUCTION	MA
46	2022-05-16	ISSUED FOR CONSTRUCTION	MA
47	2022-05-16	ISSUED FOR CONSTRUCTION	MA
48	2022-05-16	ISSUED FOR CONSTRUCTION	MA
49	2022-05-16	ISSUED FOR CONSTRUCTION	MA
50	2022-05-16	ISSUED FOR CONSTRUCTION	MA
51	2022-05-16	ISSUED FOR CONSTRUCTION	MA
52	2022-05-16	ISSUED FOR CONSTRUCTION	MA
53	2022-05-16	ISSUED FOR CONSTRUCTION	MA
54	2022-05-16	ISSUED FOR CONSTRUCTION	MA
55	2022-05-16	ISSUED FOR CONSTRUCTION	MA
56	2022-05-16	ISSUED FOR CONSTRUCTION	MA
57	2022-05-16	ISSUED FOR CONSTRUCTION	MA
58	2022-05-16	ISSUED FOR CONSTRUCTION	MA
59	2022-05-16	ISSUED FOR CONSTRUCTION	MA
60	2022-05-16	ISSUED FOR CONSTRUCTION	MA
61	2022-05-16	ISSUED FOR CONSTRUCTION	MA
62	2022-05-16	ISSUED FOR CONSTRUCTION	MA
63	2022-05-16	ISSUED FOR CONSTRUCTION	MA
64	2022-05-16	ISSUED FOR CONSTRUCTION	MA
65	2022-05-16	ISSUED FOR CONSTRUCTION	MA
66	2022-05-16	ISSUED FOR CONSTRUCTION	MA
67	2022-05-16	ISSUED FOR CONSTRUCTION	MA
68	2022-05-16	ISSUED FOR CONSTRUCTION	MA
69	2022-05-16	ISSUED FOR CONSTRUCTION	MA
70	2022-05-16	ISSUED FOR CONSTRUCTION	MA
71	2022-05-16	ISSUED FOR CONSTRUCTION	MA
72	2022-05-16	ISSUED FOR CONSTRUCTION	MA
73	2022-05-16	ISSUED FOR CONSTRUCTION	MA
74	2022-05-16	ISSUED FOR CONSTRUCTION	MA
75	2022-05-16	ISSUED FOR CONSTRUCTION	MA
76	2022-05-16	ISSUED FOR CONSTRUCTION	MA
77	2022-05-16	ISSUED FOR CONSTRUCTION	MA
78	2022-05-16	ISSUED FOR CONSTRUCTION	MA
79	2022-05-16	ISSUED FOR CONSTRUCTION	MA
80	2022-05-16	ISSUED FOR CONSTRUCTION	MA
81	2022-05-16	ISSUED FOR CONSTRUCTION	MA
82	2022-05-16	ISSUED FOR CONSTRUCTION	MA
83	2022-05-16	ISSUED FOR CONSTRUCTION	MA
84	2022-05-16	ISSUED FOR CONSTRUCTION	MA
85	2022-05-16	ISSUED FOR CONSTRUCTION	MA
86	2022-05-16	ISSUED FOR CONSTRUCTION	MA
87	2022-05-16	ISSUED FOR CONSTRUCTION	MA
88	2022-05-16	ISSUED FOR CONSTRUCTION	MA
89	2022-05-16	ISSUED FOR CONSTRUCTION	MA
90	2022-05-16	ISSUED FOR CONSTRUCTION	MA
91	2022-05-16	ISSUED FOR CONSTRUCTION	MA
92	2022-05-16	ISSUED FOR CONSTRUCTION	MA
93	2022-05-16	ISSUED FOR CONSTRUCTION	MA
94	2022-05-16	ISSUED FOR CONSTRUCTION	MA
95	2022-05-16	ISSUED FOR CONSTRUCTION	MA
96	2022-05-16	ISSUED FOR CONSTRUCTION	MA
97	2022-05-16	ISSUED FOR CONSTRUCTION	MA
98	2022-05-16	ISSUED FOR CONSTRUCTION	MA
99	2022-05-16	ISSUED FOR CONSTRUCTION	MA
100	2022-05-16	ISSUED FOR CONSTRUCTION	MA

MORGAN MAPLES
9090 TRANS-CANADA HIGHWAY
CHEMUNUS, BC

LANDSCAPE
DETAILS

DATE: 22 APR 22

SCALE: 1:100

DRAWN: DO

DESIGN: DO

CHECK: MCV

(DRAWING) NUMBER:

L4

RAIL PROJECT NUMBER:

OF 4

22-076



May 16, 2022

Core Group Consultants
320-8988 Fraserston Court
Burnaby BC

scarroll@coregroupconsultants.com

Attention: Sean Carroll

Re: PMG File No.: 22-076
Morgan Maples, 9090 Trans-Canada Highway

The following cost estimate for bonding purposes was based on our Landscape Plans dated May 16, 2022

	Size	Approximate Quantity	Unit Price	Total Price
1 Earthwork:				
b) Topsoil (cost per m ³)		100	\$ 35.00	3,500.00
2 Lawn (cost per m ²)				
a) Seeded		3000	\$ 7.00	21,000.00
3 Hard Surfacing				
a) 3/4" Crushed Granite (per cubic m)		50	\$ 65.00	3,250.00
b) Engineered wood fibre (per sq. m)		160	\$ 4.20	672.00
4 Fences & Walls (cost per lin. m)				
g) 6' ht chainlink fence		1300	\$ 100.00	130,000.00
5 Furnishings (itemize) installed				
a) Bench		4	\$ 1,600.00	6,400.00
b) Picnic table		3	\$ 3,750.00	11,250.00
c) Balance logs		3	\$ 600.00	1,800.00
d) Log steppers		6	\$ 400.00	2,400.00
e) Swing set		1	\$ 4,500.00	4,500.00
6 Plant Material:				
a) Trees				
1) Malus 'Spring Snow'	5 cm cal.	5	\$ 250.00	1,250.00
2) Nyssa sylvatica	5 cm cal.	9	\$ 250.00	2,250.00
3) Acer griseum	6 cm cal.	8	\$ 300.00	2,400.00
4) Acer rubrum 'Red Sunset'	6 cm cal.	21	\$ 300.00	6,300.00
5) Acer x freemanii 'Autumn Blaze'	6 cm cal.	4	\$ 300.00	1,200.00
6) Betula nigra 'Dura Heat'	6 cm cal.	8	\$ 300.00	2,400.00
7) Liquidambar styraciflua 'Worplesdon'	6 cm cal.	30	\$ 300.00	9,000.00
8) Tilia americana 'Redmond'	6 cm cal.	23	\$ 300.00	6,900.00
9) Zelkova serrata	6 cm cal.	31	\$ 300.00	9,300.00
10) Cornus mas	2 m ht.	6	\$ 180.00	1,080.00
11) Chamaecyparis nootkatensis 'Pendula'	2 m ht.	4	\$ 200.00	800.00
12) Abies grandis	2.5 m ht.	7	\$ 220.00	1,540.00
13) Pseudotsuga menziesii	3 m ht.	9	\$ 330.00	2,970.00
14) Pinus sylvestris	3.5 m ht.	6	\$ 260.00	1,560.00
b) Shrubs / Groundcovers				
1) Lupinus polyphyllus	#1 pot	26	\$ 5.00	130.00
2) Mahonia nervosa	#1 pot	49	\$ 5.00	245.00
3) Ceanothus 'Victoria'	#2 pot	18	\$ 10.00	180.00
4) Holodiscus discolor	#2 pot	7	\$ 10.00	70.00
5) Ribes sanguineum	#2 pot	16	\$ 10.00	160.00
6) Rosa nutkana	#2 pot	30	\$ 10.00	300.00
c) Installation			50%	25,017.50
7 Mulch (cost per m ³)				
a) Bark mulch		20	\$ 39.00	780.00

8	Totals	Total for 1	3,500.00
		Total for 2	21,000.00
		Total for 3	3,922.00
		Total for 4	130,000.00
		Total for 5	26,350.00
		Total for 6	75,052.50
		Total for 7	780.00
		TOTAL	\$ 260,604.50


Please note that this is only an estimate, and is subject to change due to economic conditions, availability of materials, and actual site conditions at the time of construction.

Yours truly,

Scott Archer
PMG Landscape Architects Ltd.

Reviewed By: Mary Chan Yip

Schedule 3 - MHP00001 - Landscaping Plan and Security - PMG Landscape Architects May 16, 2022 (8 pages)



MODULAR HOME DEVELOPMENT 9090 ISLAND HIGHWAY CHEMAINUS, BC

BUILDING PERMIT PLANS - SITE SERVICING

LEGAL DESCRIPTION:

THE EAST 60 ACRES OF SECTION 10, RANGE 5, CHEMAINUS DISTRICT,
EXCEPT 16.5 FOOT STRIP ALONG AND ADJOINING THE NORTH AND EAST BOUNDARIES THEREOF,
RESERVED FOR ROAD PURPOSES, EXCEPT PARTS IN PLANS 11469, 26194 AND VP68870
PD No: 009-885-200

DEVELOPER:

1251719 B.C. LTD.
320-8988 FRASERTON COURT
BURNABY, BC V5J 5H8
TEL: 604-299-0605

CONSULTANT:

CoreGroup
LAND DEVELOPMENT SERVICES
320-8988 FRASERTON COURT
BURNABY, BC V5J 5H8
TEL: (604) 299-0605 FAX: (604) 299-0605
Email: info@coregroup.ca 10/01/2017 (20)





PROJECT LOCATION MAP


NOT TO SCALE



DRAWING LIST:

1. SITE PLAN
2. SITE SERVICING PLAN
3. SITE GRADING PLAN
4. FIRE SUPPRESSION PLAN
5. ROADWORKS, GRADING, WATERWORKS
6. ROADWORKS, GRADING, WATERWORKS
7. ROADWORKS, GRADING, WATERWORKS
8. ROADWORKS, GRADING, WATERWORKS
9. STORM AND SANITARY WORKS
10. STORM AND SANITARY WORKS
11. STORM AND SANITARY WORKS
12. STORM AND SANITARY WORKS
13. STORMWATER MANAGEMENT PLAN
14. STORMWATER MANAGEMENT PLAN
15. STREETLIGHT AND SIGNAGE PLAN
16. EROSION AND SEDIMENT CONTROL PLAN - STAGE 1
17. EROSION AND SEDIMENT CONTROL PLAN - STAGE 2
18. EROSION AND SEDIMENT CONTROL PLAN - STAGE 3
19. EROSION AND SEDIMENT CONTROL PLAN - STAGE 4
20. GARBAGE ENCLOSURE AND MAIL KIOSK DETAILS
21. NOTES AND DETAILS
- 21A. LOT BUILDOUT PHASING PLAN

Schedule 4 - MHP00001 - Servicing Plan - Modular Home Development Core Group August 17 2023 (23 pages)

[illegible]





LEGAL DESCRIPTION:

THE EAST 80 ACRES OF SECTION 10, RANGE 3,
CHENANUIS DISTRICT,
EXCEPT 16.5 FOOT STRIP ALONG AND ADJOINING
THE NORTH AND EAST BOUNDARIES THEREOF,
RESERVED FOR ROAD PURPOSES, EXCEPT PARTS IN
PLATS 11496, 26194 AND WPM8870
PD No. 308-883-200

CIVIC ADDRESS :
8000 ISLAND HIGHWAY, CHEMANUVE, BC

LEGEND



PROP. WATER

PROP. HYDRANT

HYDRANT COVER

[illegible]

Schedule 4 - MHP00001 - Servicing Plan - Modular Home Development Core Group August 17 2023 (23 pages)



NOTES

- [illegible]



LEGEND	
BEGINNING OF CURVE	PC
END OF CURVE	PT
POINT OF VERTICAL HORIZONTAL CURVE	PVI
POINT OF HORIZONTAL VERTICAL CURVE	HVC
START OF VERTICAL CURVE	SVC
COMPOUND VERTICAL CURVE	CVC
END OF VERTICAL CURVE	EVC
HIGH POINT	HP
LOW POINT	LP
GRADE BREAK	GB
CATCH BASIN	CB
FROM LEFT CORNER TIE:	
WFOF 30.60 TIE	
PRSR, SRD ELEVATION	
PRSR, TAFTI FROM (S)	
PRSR, SLOPING (SLOPE) WATER	

ELEVATION DATA: ELEVATIONS ARE DERIVED FROM GPS OBSERVATIONS, LOCAL BENCHMARK ESTABLISHED DURING CONSTRUCTION OF SECTION 10A (HEREINAFTER) OR THE NEAREST EXISTING BENCHMARK TO THE NEAREST PLAIN (HEREINAFTER).	<div style="border: 1px solid black; padding: 5px; text-align: center;"> LEGAL DESCRIPTION </div> <p>THE EAST 1/4 ACRES OF SECTION 10, RANGE 5, TOWNSHIP 36N, COUNTY OF BUTTE, MT. (HEREINAFTER) (THE "PROPERTY") IS BEING OFFERED FOR SALE TO THE PUBLIC BY THE BUTTE COUNTY BOARD OF SUPERVISORS. THE PROPERTY IS BEING OFFERED FOR SALE TO THE PUBLIC BY THE BUTTE COUNTY BOARD OF SUPERVISORS.</p>	GRAPHIC SCALE: <div style="text-align: center;">  GRAPHIC SCALE SCALE: 1" = 50' </div>	DEVELOPER: <div style="text-align: center;">  CoreGroup 1251970 BAC, LTD. 3000 W. 10TH AVENUE, SUITE 100 DENVER, CO 80202 TEL: 303.733.1000 FAX: 303.733.1001 WWW.COREGROUP.COM </div>	DISTRICT OF NORTH COWICHAN MORGAN MAPLES ROADWORKS, GRADING, WATER AND FIRE SUPPRESSION PLAN SHEET 5 OF 21
---	---	--	--	--



LEGEND	
REPAIRING OF CURB	PC
END OF CURVE	PT
POINT OF REVERSE HORIZONTAL CURVE	PRC
POINT OF COMPOUND HORIZONTAL CURVE	PVC
START OF VERTICAL CURVE	BVC
COMPOUND VERTICAL CURVE	CVC
END OF VERTICAL CURVE	EVC
HIGH POINT	HP
LOW POINT	LP
CURVE BREAK	CB
CATCH BASIN	CB
PREP. LEFT SIDEWAY SLAY	CS
PREP. SLAY TIE	ST
PREP. BRID. DECK/ROW	BR
PREP. DITCH FASHION LANE	DF
PREP. DRAINAGE (GRAVEL) WATER	WD

[illegible]

[illegible]

NOTES




17 2023 (23 pages)	
CONCRETE CURB	PC
END CURB	PC
POINT OF VIEW/REAR HORIZONTAL CURVE	PVC
POINT OF COMING/REAR HORIZONTAL CURVE	PCC
POINT OF VIEW/FRONT HORIZONTAL CURVE	PVC
COMPIRE/FRONT HORIZONTAL CURVE	PVC
END OF VERTICAL CURVE	PVC
HIGH POINT	HP
LOW POINT	LP
GRADE BREAK	MB
CATCH BASIN	CB
GRADE: LAST KNOWN ELEV	TK
PROP. SLAB LIFE	SL
PROP. SPOT ELEVATION	SE
PROP. CATCH BASIN	CB
PROP. TOPOGRAPHY (DISTANCE) MILES	MP

IN THE CONSTRUCTION NOTICE

- [illegible]



TRANS-CANADA HIGHWAY

[illegible]

GENOTYPING DATA

ELEVATIONS ARE DERIVED FROM GPS OBSERVATIONS. LOCAL BENCHMARK ESTABLISHED ON/ON CENTER OF SECTION 30, TOWNSHIP 17 N, RANGE 10 E, COUNTY OF CHRYSLER PARCELS, 16 NEPTUNUS (PLAN 02/25/01)

BENCHMARK DATA:				
ELEVATIONS OBTAINED FROM GPS				
OBSERVATIONS LOCAL BENCHMARK				
ESTABLISHED ORIGIN CENTER OF SECTION				
AL. TURNPIKE 17 ON HELLON POINT				
DISTANCE TABLE 6.0 METER/INCH PLAN				
1	2013/01/21	SW	SW	ROADSIDE FOR MEASURING POINT
2	2013/01/21	SW	SW	ROADSIDE FOR MEASURING
REDO (S&S) (S&S) (S&S) (S&S)				

LEGAL DESCRIPTION

THE EAST 80 ACRES OF SECTION 10, RANGE 5,
CHEMANUS DISTRICT, EXCEPT 16.5 FOOT STRIP
ALONG AND ADJOINING THE NORTH AND EAST
BOUNDARIES, THENCE, RESERVED FOR ROAD
RIGHTS, EXCEPT 5 ACRES IN PLANS 11486,
20-54 AND 180503 TO 180506, D.M. 55-57C

GRAPHIC SCALE:



DEVELOPER
1250719 B.C. LTD.
8000 FRANKFORD AVENUE
SURREY, B.C. V5A 2H8
TEL: 454-379-7600

CoreGroup
CONSULTANTS
LAND DEVELOPMENT SERVICES
(303) 688-7400 (FACSIMILE: 303) 688-7401



DISTRICT OF NORTH COWICHAN

MORGAN MABLES

ROADWORKS, GRADING, WATER AND FIRE SUPPRESSION PLAN


FILE	
CONSULTANTS	
DWG NO.	2087
CITY	CHICAGO

[illegible][illegible]



BENCHMARK DATA:					
ELEVATIONS ARE DERIVED FROM GPS OBSERVATIONS. LOCAL BENCHMARK ESTABLISHED NEAR CENTER OF SECTION AL. TURNPIKE 17 IN WILSON TOWNSHIP, DECATUR COUNTY, NC. INFORMATION POINT DECATUR PARKING, NC. INFORMATION POINT 03/25/2015					
1. 2015/01/24	30	30	30	30	30
2. 2015/01/24	30	30	30	30	30
3. 2015/01/24	30	30	30	30	30

LEGAL DESCRIPTION
THE EAST 60 ACRES OF SECTION 10, RANGE 5,
CHEMANUS DISTRICT, EXCEPT 16.5 FOOT STRIP
ALONG AND ADJOINING THE NORTH AND EAST
BOUNDARIES, THUSLEY, RECEIVED FOR ROAD
RIGHT-OF-WAY, SACKETT HWY. (Rd. 1144),
20154 AND 16101020 T. 44N. 05N-07E



DEVELOPER
1250719 B.C. LTD.
305-BRIDGE FRANKFORD / ONTARIO
DURHAM, ON M3A 2M8
TEL: 404-738-7000

CoreGroup
CONSULTANTS
(LAND DEVELOPMENT SERVICES)
370-8888 (KASINGTON COURT)
FARMER, NC 27534
tel. (304)259-0015 fax (304)299-0629
internet: jg@coregroup.com



DISTRICT OF NORTH COWICHAN		
COUNCILMAN - 08 TAXMAN - 08 METRIC SCALE - 0.004 HYDRAULIC - 78 DATE - AUG. 14, 2013	MORGAN MAPLES STORM AND SANITARY WORKS 888 GLEN HEAVY, CHEMUNG, BC	PLAN - PERMIT/TAPE 2087 CITY SOC. NO. - CHEMUNG SHEET 9 OF 21



TRANS-CANADA HIGHWAY




1. SEE SHEET 20 FOR NOTES.


- THE NEW DEVELOPMENT LTD. BRANDED FOR THE BEST
AND HIGHEST LIT. COLLECTION EVER! A FINE DESIGN.**
- THE NEW DESIGN IS WORKING FOR
YOURSELF AND YOUR BUSINESS!**

[illegible]



Schedule 4 - MHP00001 - Servicing Plan - Modular Home Development Core Group August 17 2023 (23 pages)






- 1. SET B.E. HYDRO REGULATORS FOR SERVICE CONNECTION DETAILS.
- 2. CONSTRUCTION TO ACHIEVE EXACT SERVICE LOCATIONS WITH B.E. HYDRO TO COMMENCE CONSTRUCTION.
- 3. ALL LAMINATES TO HAVE BRASS/STAINLESS POLYURETHANE INTRACTORS.
- 4. ALL POLES TO BE HOT-DIP GALVANIZED AND POWER COATED WITH GRAY COLOUR PAINTS.
- 5. LAMINATES SHALL INCLUDE ALL NECESSARY WELD CONNECTIONS WITHIN CONSTRUCTION.
- 6. CONTRACTOR TO ENSURE THAT ALL STREET LIGHT POLES ARE A MINIMUM 5.0M CLEAR OF ALL HOV LANE POLES AND OVERHEAD PRIMARY WIRES & 0.3M CLEAR OF ALL OVERHEAD SECONDARY WIRES PRIOR TO INSTALLING BASES.
- 7. ALL STREET LIGHTS TO BE INSTALLED 0.3M CLEAR OF ALL HOV LANE POLES.
- 8. CONTRACTOR TO PROVIDE SHOP DRAWINGS OF STREETLIGHTS AND POLES FOR APPROVAL BY THE HOV CONTRACTOR.
- 9. CONTRACTOR TO VERIFY LOCATIONS 3 MONTHS PRIOR TO START OF CONSTRUCTION FOR STREET LIGHTS.

LEGEND

PROPOSED 6' HIGH POST-TOP STREETLIGHT 30W LED LUMINAIRE PER
UNION CONCEPT SERIES CATALOGUE @ 30W=18,000-30W-32
NOT COMPLAINT ON TYPE OR CHANGE CLASS
PEDESTAL CONDUIT TO BE 30"=HYD. CONTAINING 1 IN. 3/4" ALUMINUM
1/4" ALUMINUM BOND U-BOLTS TO BE ON ALTERNATING PHASE CONDUCTORS
100%/240V SERVICE BASED WITH PHOTOCELL & FUSES TO BE FIELD-LOCATED
ON/NEAR NEAR HYDRO FEEDPOINT.
(OR APPROVED EQUAL)

[illegible]

STAGE 2 - EARTHWORKS

[illegible][illegible]



- [illegible]

MAINTENANCE ALL STAGES (AS APPLICABLE)

1. GROUND ACCESS PATHS TO BE INSPECTED DAILY TO ENSURE FUNCTIONALITY, AND ADDITIONAL ROADS AS REQUIRED.
2. THE CONTRACTOR MUST REGULARLY CLEAN PAVED ROAD SURFACES OF ACCUMULATED SEDIMENTS AT THE END OF EACH DAY OR AS REQUIRED, NO SOIL, SAND OR OTHER MATERIAL, WITH A HIGH SEDIMENT RISK, SHALL BE DEPOSITED OR PILED OUTSIDE OF THE PROPERTY BOUNDARIES, PARTICULARLY ON PAVED ROAD SURFACES.
3. SEDIMENT FENCES/BARRIERS TO BE INSPECTED AND REPAIRED PRIOR TO EXPECTED RAIN EVENTS AND FOLLOWING ALL SIGNIFICANT STORM EVENTS OR PERIODS OF EXTENDED RAIN. ACCUMULATED SEDIMENTS GREATER THAN 3" OF THE FENCE CAPACITY OR DEFICIENCIES SHOULD BE DEALT WITH ACCORDINGLY.
4. ALL SEDIMENT REMOVED FROM ESC CONTROL FACILITIES TO BE DISPOSED OF IN A MANNER AS TO NOT COMPOUND OR COMPROMISE THE SEDIMENT LOADING OF OTHER CONTROL MEASURES.

UTILITY AND ROAD WORKS INSTALLATION STAGE

1. ALL ACCESS TO AND FROM SITE TO BE FROM THE RESTRICTED ENTRY-EXIT POINTS.
2. ESC SUPERVISOR TO CONDUCT MONITORING AS PER THE CITY OF SURREY MONITORING AND REPORTING REQUIREMENTS.
3. CONTRACTOR TO ENSURE THAT ESC MEASURES ARE WELL MAINTAINED, CLEARED, REPAIRED, OR REPLACED AS REQUIRED.
4. CONTRACTOR TO CO-ORDINATE THE ELIMINATION OF TEMPORARY ESC FACILITIES IF THEY ARE NO LONGER REQUIRED OR TO FACILITATE SITE OPERATIONS WITH THE ESC SUPERVISOR. ADDITIONAL ESC FACILITIES MAY NEED TO BE INSTALLED AS PER THE DIRECTION OF THE ESC SUPERVISOR.
5. DISPOSED VEHICLE-TRAVELED ROAD AREAS TO BE ANNOUESED WITH MIN. 100MM THICK LAYER OF 10-20mm CRUSHED GRAVEL TO PREVENT EROSION AND TRACKING OF SILTATEOUS MATERIAL.

WET WEATHER SHUT DOWN

WET WEATHER SHUT DOWN PROCEDURES ARE TO BE IMPLEMENTED IF A RAIN EVENT IN EXCESS OF 25mm IN A 24-HOUR PERIOD FORECAST. ADDITIONALLY, REACTIVE WET WEATHER SHUT DOWNS ARE TO BE IMPLEMENTED WHERE THE INTENSITY AND/OR DURATION OF THE PRECIPITATION RESULTS IN THE SATURATION OF THE OVERLAYING SURFACE MATERIAL, AND SIGNIFICANT PONDING OR SURFACE RUN OFF OCCURS.

UNDERLYING SOIL IS SAND AND SILTY SAND

[illegible]

STAGE 4 - MODULAR INSTALLATION & DECOMMISSIONING



- [illegible]

MAINTENANCE ALL STAGES (AS APPLICABLE)

1. GRIKES ACCESS PADS TO BE INSPECTED DAILY TO ENSURE FUNCTIONALITY, ADDITIONAL BOOK AS REQUIRED.
2. THE CONTRACTOR MUST REGULARLY CLEAN PAVED ROAD SURFACES OF ACCUMULATED SEDIMENTS AT THE END OF EACH DAY OR AS REQUIRED. NO SOIL, SAND OR OTHER MATERIAL WITH A HIGH SEDIMENT CONTENT SHALL BE DEPOSITED OR PILED OUTSIDE OF THE PROPERTY BOUNDARIES, PARTICULARLY ON PAVED ROAD SURFACES.
3. SEDIMENT FENCES/BARRIERS TO BE INSPECTED AND REPAIRED PRIOR TO EXPECTED RAIN EVENTS AND FOLLOWING ALL SIGNIFICANT STORM EVENTS OR PERIODS OF EXTENDED RAIN. ACCUMULATED SEDIMENTS GREATER THAN 30% OF THE FENCE CAPACITY OR OBSTRUCTIONS SHOULD BE DEALT WITH ACCORDINGLY.
4. ALL SEDIMENT REMOVED FROM EROSION CONTROL FACILITIES TO BE DISPOSED OF IN A MANNER AS TO NOT

BUILDING CONSTRUCTION & LANDSCAPING

1. GENERAL CONTRACTOR TO ENSURE THAT STORMWATER CONVEYANCE CHANNELS AND DISCHARGE POINTS TO ADJACENT STREAMS, DITCHES, OR ENTRY POINTS TO PIPED NETWORKS, ARE ADEQUATELY PROTECTED.
2. CONTRACTOR TO ENSURE THAT ESC FACILITIES SPECIFIED IN THE ESC PLAN OR ANY ADDENDUMS ARE IMPLEMENTED ACCORDINGLY.
3. AFTER FINAL LOT GRADING IS COMPLETED ALL DISTURBED AREAS ARE TO BE PROTECTED AS PER THE ESC PLAN.
4. EXPOSED VEHICLE-TRAVELED WORK AREAS TO BE ARMOURRED WITH MIN. 150mm THICK LAYER OF 10-50mm CRUSHED GRAVEL TO PREVENT EROSION AND TRACKING OF SILT-LADEN MATERIAL.




LEADING

PROFESSOR SAJ FENC

CANDIDATE SECURITY TESTS WORTHY

1992-1993

[illegible]

[illegible]

Schedule 4 - MHP00001 - Servicing Plan - Modular Home Development Core Group August 17 2023 (23 pages)


- [illegible]


[illegible]

- ALL TESTING TO BE PERFORMED BY A CSA OR CLO, EXHAUSTION CERTIFIED TESTING LABORATORY/ENGINEER/CONSULTANT.
- FREQUENCY OF ENDOXY TESTS FOR HGT-MAX ADHESIVE SHALL BE ONE TEST PER 500 LINAL METERS OR TWENTY PER METER OF DEPTH, RESPECTIVELY.
- FREQUENCY OF ENDOXY TESTS FOR ROADWAY EXHAUSTION, EXHAUSTION SHALL BE ONE TEST PER 500 LINAL METERS OR TWENTY PER METER OF DEPTH.
- TESTS FOR 200 μ W FOR 300mm LPT.
- TESTS FOR 200 μ W FOR 300mm LPT.
- SLAB-SHAPE SHALL BE ONE TEST PER 500 LINAL METERS OF LANE WIDTH AND ONE TEST PER 500 LINAL METERS OF DEPTH, LEFT OR OF SPOILED THREACHES.
- TESTS FOR 200 μ W FOR 300mm LPT.
- TESTS FOR 200 μ W FOR 300mm LPT.
- FREQUENCY OF ENDOXY TESTS FOR HGT-MAX ADHESIVE SHALL BE ONE TEST PER 500 LINAL METERS OR TWENTY PER METER OF DEPTH, RESPECTIVELY.
- FREQUENCY OF ENDOXY TESTS FOR HGT-MAX ADHESIVE SHALL BE ONE TEST PER 500 LINAL METERS OR TWENTY PER METER OF DEPTH, RESPECTIVELY.
- CONCRETE PAVING SHALL BE ONE TEST PER 500 TONNES OF MAX LANE WIDTH AND ONE TEST PER 500 TONNES OF MAX LANE DEPTH.
- STREET PAVING, CONC LOCATIONS WILL BE SELECTED FOR EACH PASS OF THE PAVING MACHINE AS FOLLOWS:
 1. DIVIDE THE CONC LOCATIONS TO BE SELECTED RANDOMLY FROM ONE - SIXTY INCREMENTS.
 2. CONC LOCATIONS TO BE SELECTED RANDOMLY FROM ONE - SIXTY INCREMENTS.
 3. CONC LOCATIONS TO BE SELECTED RANDOMLY FROM ONE - SIXTY INCREMENTS.
- FOR OTHER PAVING OPERATIONS, A MINIMUM OF ONE CONC DATA POINT SHALL BE OBTAINED.

11. SHALL BE ONE TEST PER 300 LINEAR METRES OF A MINIMUM OF ONE PER DAY.
12. SANITARY SEWER MAINS TO BE VIDEO INSPECTED & PRESSURE TESTED FOR MAND.
13. STORM SEWERS TO BE VIDEO INSPECTED FOR MAND.
14. WATER SERVICE / MAIN PRESSURE AND BACTERIOLOGICAL TESTING TO BE DONE BY CONTRACTOR PRIOR TO TIE-IN AND ACCEPTANCE BY ENGINEER. ASSURED TEST PRESSURE OF 1200 KPa (200 psi).
15. ALL TESTING OF WATER MAIN / SERVICES TO BE DONE AND APPROVED BEFORE BACKFILLING PIPE AND TYING IN TO EXISTING WATER SERVICE MAIN.
16. BACKFILL PREVENTERS IN WATER CHAMBERS TO BE TESTED AND CERTIFIED TO SHOW LANTS ARE IN PROPER WORKING ORDER.

11. SHALL BE ONE TEST PER 300 LINEAR METRES OF A MINIMUM OF ONE PER DAY.
12. SANITARY SEWER MAINS TO BE VIDEO INSPECTED & PRESSURE TESTED FOR MAND.
13. STORM SEWERS TO BE VIDEO INSPECTED FOR MAND.
14. WATER SERVICE / MAIN PRESSURE AND BACTERIOLOGICAL TESTING TO BE DONE BY CONTRACTOR PRIOR TO TIE-IN AND ACCEPTANCE BY ENGINEER. ASSURED TEST PRESSURE OF 1200 KPa (200 psi).
15. ALL TESTING OF WATER MAIN / SERVICES TO BE DONE AND APPROVED BEFORE BACKFILLING PIPE AND TYING IN TO EXISTING WATER SERVICE MAIN.
16. BACKFILL PREVENTERS IN WATER CHAMBERS TO BE TESTED AND CERTIFIED TO SHOW LANTS ARE IN PROPER WORKING ORDER.

[illegible][illegible]



THE EAST 60 ACRES OF SECTION 10, RANGE 5,
CHEMANUS DISTRICT,
EXCEPT 16.5 FOOT STRIP ALONG AND ADJOINING
THE NORTH AND EAST BOUNDARIES, THEREBY,
RESERVED FOR ROAD PURPOSES, EXCEPT PLOTS H
PLANS 11480, 20194 AND 495800.

HOBO BLAND HIGHWAY, CREWMAVE, WA

A vertical color scale legend with seven entries, each consisting of a colored square followed by a phase label. The colors transition from red at the top to purple at the bottom.

PHASE 1	Red
PHASE 2	Orange
PHASE 3	Yellow
PHASE 4	Green
PHASE 5	Blue
PHASE 6	Pink
PHASE 7	Purple

[illegible]

BRITISH COLUMBIA BUILDING CODE 2018

SCHEDULE B

Forming Part of Subsection 2.2.7, Division C of the
British Columbia Building Code

Building Permit Number
(for authority having jurisdiction's use)

ASSURANCE OF PROFESSIONAL DESIGN AND COMMITMENT FOR FIELD REVIEW

- Notes: (i) This letter must be submitted prior to the commencement of construction activities of the components identified below. A separate letter must be submitted by each *registered professional of record*.
(ii) This letter is endorsed by: Architectural Institute of BC, Association of Professional Engineers and Geoscientists of the Province of BC, Building Officials' Association of BC, and Union of BC Municipalities.
(iii) In this letter the words in italics have the same meaning as in the British Columbia Building Code.

To: The *authority having jurisdiction*

District of North Cowichan

Name of Jurisdiction (Print)

Re: Morgan Maples

Name of Project (Print)

9090 Island Highway, Chemainus, BC

Address of Project (Print)

The undersigned hereby gives assurance that the design of the

(Initial those of the items listed below that apply to this *registered professional of record*. All the disciplines will not necessarily be employed on every project.)

_____ ARCHITECTURAL
_____ STRUCTURAL
_____ MECHANICAL
aw _____ PLUMBING — SITE SERVICES
_____ FIRE SUPPRESSION SYSTEMS
_____ ELECTRICAL
_____ GEOTECHNICAL — temporary
_____ GEOTECHNICAL — permanent



(Professional's Seal and Signature)

February 21, 2023

Date

components of the plans and supporting documents prepared by this *registered professional of record* in support of the application for the *building* permit as outlined below substantially comply with the British Columbia Building Code and other applicable enactments respecting safety except for construction safety aspects.

The undersigned hereby undertakes to be responsible for *field reviews* of the above referenced components during construction, as indicated on the "SUMMARY OF DESIGN AND FIELD REVIEW REQUIREMENTS" below.

CRP's Initials

BRITISH COLUMBIA BUILDING CODE 2018

Schedule B - Continued

Building Permit Number
(for authority having jurisdiction's use)

9090 Island Highway, Chemainus, BC

Project Address

Plumbing - Site Services

Discipline

The undersigned also undertakes to notify the *authority having jurisdiction* in writing as soon as possible if the undersigned's contract for *field review* is terminated at any time during construction.

I certify that I am a *registered professional* as defined in the British Columbia Building Code.

Cormac Nolan P.Eng

Registered Professional of Record's Name (Print)

320 -8988 Fraserton Court

Address (Print)

Burnaby, BC

Address (Print) (continued)

604 299-0605

Phone Number



(Professional's Seal and Signature)

February 21, 2023

Date

(If the *Registered Professional of Record* is a member of a firm, complete the following)

I am a member of the firm Core Group Civil Consultants Ltd Permit To Practice # 1001017(BC)
and I sign this letter on behalf of the firm. (Print name of firm)

Note: The above letter must be signed by a *registered professional of record*, who is a *registered professional*. The British Columbia Building Code defines a *registered professional* to mean

- (a) a person who is registered or licensed to practise as an architect under the Architects Act, or
- (b) a person who is registered or licensed to practise as a professional engineer under the Engineers and Geoscientists Act.

CRP's Initials

BRITISH COLUMBIA BUILDING CODE 2018

Schedule B - Continued

Building Permit Number
(for authority having jurisdiction's use)9090 Island Highway, Chemainus, BC
Project AddressPlumbing - Site Services
Discipline

SUMMARY OF DESIGN AND FIELD REVIEW REQUIREMENTS

(Initial applicable discipline below and cross out and initial only those items not applicable to the project.)

ARCHITECTURAL

- 1.1 Fire resisting assemblies
- 1.2 *Fire separations and their continuity*
- 1.3 *Closures, including tightness and operation*
- 1.4 Egress systems, including *access to exit* within suites and floor areas
- 1.5 Performance and physical safety features (guardrails, handrails, etc.)
- 1.6 Structural capacity of architectural components, including anchorage and seismic restraint
- 1.7 Sound control
- 1.8 Landscaping, screening and site grading
- 1.9 Provisions for firefighting access
- 1.10 Access requirements for *persons with disabilities*
- 1.11 Elevating devices
- 1.12 Functional testing of architecturally related fire emergency systems and devices
- 1.13 Development Permit and conditions therein
- 1.14 Interior signage, including acceptable materials, dimensions and locations
- 1.15 Review of all applicable shop drawings
- 1.16 Interior and exterior finishes
- 1.17 Dampproofing and/or waterproofing of walls and slabs below grade
- 1.18 Roofing and flashings
- 1.19 Wall cladding systems
- 1.20 Condensation control and cavity ventilation
- 1.21 Exterior glazing
- 1.22 Integration of building envelope components
- 1.23 Environmental separation requirements (Part 5)
- 1.24 Building envelope, Part 10 – ASHRAE, NECB or Energy Step Code requirements
- ~~1.25 Building envelope, testing, confirmation or both as per Part 10 requirements~~



February 21, 2023

Date

STRUCTURAL

- 2.1 Structural capacity of structural components of the *building*, including anchorage and seismic restraint
- 2.2 Structural aspects of *deep foundations*
- 2.3 Review of all applicable shop drawings
- ~~2.4 Structural aspects of unbonded post-tensioned concrete design and construction~~

MECHANICAL

- 3.1 HVAC systems and devices, including high *building* requirements where applicable
- 3.2 *Fire dampers* at required *fire separations*
- 3.3 Continuity of *fire separations* at HVAC penetrations
- 3.4 Functional testing of mechanically related fire emergency systems and devices
- 3.5 Maintenance manuals for mechanical systems
- 3.6 Structural capacity of mechanical components, including anchorage and seismic restraint
- 3.7 Review of all applicable shop drawings
- 3.8 Mechanical systems, Part 10 – ASHRAE, NECB or Energy Step Code requirements
- ~~3.9 Mechanical systems, testing, confirmation or both as per Part 10 requirements~~

CRP's Initials

BRITISH COLUMBIA BUILDING CODE 2018

Schedule B - Continued

Building Permit Number
(for authority having jurisdiction's use)

9090 Island Highway, Chemainus, BC

Project Address

Plumbing - Site Services

Discipline

PLUMBING

- 4.1 ~~Roof drainage systems~~
- 4.2 ~~Site and foundation drainage systems~~ SERVICES
- 4.3 ~~Plumbing systems and devices~~
- 4.4 Continuity of ~~fire separations~~ at plumbing penetrations
- 4.5 Functional testing of plumbing related fire emergency systems and devices
- 4.6 Maintenance manuals for ~~plumbing systems~~
- 4.7 Structural capacity of plumbing components, including anchorage and seismic restraint
- 4.8 Review of all applicable shop drawings
- 4.9 Plumbing systems, Part 10 – ASHRAE, NECB or Energy Step Code requirements
- 4.10 ~~Plumbing systems, testing, confirmation or both as per Part 10 requirements~~

FIRE SUPPRESSION SYSTEMS

- 5.1 Suppression system classification for type of occupancy
- 5.2 Design coverage, including concealed or special areas
- 5.3 Compatibility and location of electrical supervision, ancillary alarm and control devices
- 5.4 Evaluation of the capacity of city (municipal) water supply versus system demands and domestic demand, including pumping devices where necessary
- 5.5 Qualification of welder, quality of welds and material
- 5.6 Review of all applicable shop drawings
- 5.7 Acceptance testing for "Contractor's Material and Test Certificate" as per NFPA Standards
- 5.8 Maintenance program and manual for suppression systems
- 5.9 Structural capacity of sprinkler components, including anchorage and seismic restraint
- 5.10 For partial systems — confirm sprinklers are installed in all areas where required
- 5.11 Fire Department connections and hydrant locations
- 5.12 Fire hose standpipes
- 5.13 Freeze protection measures for fire suppression systems
- 5.14 ~~Functional testing of fire suppression systems and devices~~

ELECTRICAL

- 6.1 Electrical systems and devices, including high building requirements where applicable
- 6.2 Continuity of ~~fire separations~~ at electrical penetrations
- 6.3 Functional testing of electrical related fire emergency systems and devices
- 6.4 Electrical systems and devices maintenance manuals
- 6.5 Structural capacity of electrical components, including anchorage and seismic restraint
- 6.6 Clearances from buildings of all electrical utility equipment
- 6.7 Fire protection of wiring for emergency systems
- 6.8 Review of all applicable shop drawings
- 6.9 Electrical systems, Part 10 – ASHRAE, NECB or Energy Step Code requirements
- 6.10 ~~Electrical systems, testing, confirmation or both as per Part 10 requirements~~

GEOTECHNICAL — Temporary

- 7.1 Excavation
- 7.2 Shoring
- 7.3 Underpinning
- 7.4 ~~Temporary construction dewatering~~

GEOTECHNICAL — Permanent

- 8.1 Bearing capacity of the soil
- 8.2 Geotechnical aspects of deep foundations
- 8.3 Compaction of engineered fill
- 8.4 Structural considerations of soil, including slope stability and seismic loading
- 8.5 Backfill
- 8.6 Permanent dewatering
- 8.7 ~~Permanent underpinning~~



February 21, 2023

Date

CRP's Initials



GEOPACIFIC

604.439.0922
1779 W 75th Avenue
Vancouver, B.C V6P 6P2

Core Group Civil Consultants Ltd.
#320 – 8988 Fraserton Court
Burnaby, BC
V5J 5H8

February 11, 2022
File: 18529

Attention: Dylan Bryson

**Re: Geotechnical Comments on Proposed Stormwater Management Systems
Proposed Modular Home Park - 9090 Island Highway, Chemanius, BC**

We understand our comments are required regarding the stormwater management systems proposed onsite and their impact on the groundwater regime and slope stability. We understand each modular home lot will have a raingarden and infiltration gallery to direct water into the ground across the development. We further understand grade changes are proposed across the site with grade increases of up to 9 m towards the south, and grade decreases of up to 8 m to the north.

GeoPacific previously completed a test pit investigation of the subsurface and groundwater conditions on February 23 and 24, 2021. At that time, a total of 22 test pits were excavated across the site between 0.8 m and 3.5 m below current site grades, including two infiltration tests near the centre of site. The results of our investigation are outlined in our Geotechnical Investigation Report, dated March 9, 2021. The subsurface soil conditions across the site generally consist of a layer of topsoil, overlying compact to dense sand to very stiff sandy silt. Some rock outcrops were observed along the west side of site. The static groundwater table was not encountered during the investigation. Some perched groundwater is expected to occur on the boundary of the till-like soils. We expect the stormwater management systems will be located in the native sand to sandy silt, or engineered fill.

We have reviewed the Rainwater Management Plan Report (dated January 24, 2022), provided by Core Group Civil Consultants Ltd. The report indicates stormwater will be managed through the use of stormwater infiltration and detention systems.

Based on the grading plan provided, we expect some permanent slopes will be present. From a geotechnical perspective, we recommend any infiltration galleries have a minimum setback of 5 m away from the top of any permanent slope and be located a minimum of 2 m above the static groundwater table or bedrock contact. If these conditions cannot be met, then stormwater detention systems should be employed in these areas. GeoPacific intends to review the conditions during construction, as outlined in our Geotechnical Investigation Report, to confirm the subsurface conditions on the lots and provide additional recommendations as necessary. Given the above, both stormwater management by infiltration and/or detention is feasible from a geotechnical perspective and an acceptable level of slope stability will be maintained.

We are pleased to be of assistance to you on this project and we trust that our comments and recommendations are both helpful and sufficient for your current purposes. If you would like further details or would like clarification of any of the above, please do not hesitate to call.

For:
GeoPacific Consultants Ltd.

Austin Lockstidt, B.A.Sc., EIT
Engineer In Training

Kevin Bodnar, M.Eng., P.Eng.
Principal

BRITISH COLUMBIA BUILDING CODE 2018

SCHEDULE B

Forming Part of Subsection 2.2.7., Division C of the
British Columbia Building Code

Building Permit Number
(for authority having jurisdiction's use)

ASSURANCE OF PROFESSIONAL DESIGN AND COMMITMENT FOR FIELD REVIEW

- Notes: (i) This letter must be submitted prior to the commencement of construction activities of the components identified below. A separate letter must be submitted by each *registered professional of record*.
(ii) This letter is endorsed by: Architectural Institute of BC, Association of Professional Engineers and Geoscientists of the Province of BC, Building Officials' Association of BC, and Union of BC Municipalities.
(iii) In this letter the words in italics have the same meaning as in the British Columbia Building Code.

To: The *authority having jurisdiction*

District of North Cowichan

Name of Jurisdiction (Print)

Re: Morgan Maples

Name of Project (Print)

9090 Island Highway, Chemainus, BC

Address of Project (Print)

The undersigned hereby gives assurance that the design of the

(Initial those of the items listed below that apply to this *registered professional of record*. All the disciplines will not necessarily be employed on every project.)

☐ ARCHITECTURAL
☐ STRUCTURAL
☐ MECHANICAL
☐ PLUMBING
☐ FIRE SUPPRESSION SYSTEMS
☐ ELECTRICAL
☒ GEOTECHNICAL — temporary
☒ GEOTECHNICAL — permanent



(Professional's Seal and Signature)

June 1, 2021

Date

components of the plans and supporting documents prepared by this *registered professional of record* in support of the application for the *building* permit as outlined below substantially comply with the British Columbia Building Code and other applicable enactments respecting safety except for construction safety aspects.

The undersigned hereby undertakes to be responsible for *field reviews* of the above referenced components during construction, as indicated on the "SUMMARY OF DESIGN AND FIELD REVIEW REQUIREMENTS" below.

CRP's Initials

BRITISH COLUMBIA BUILDING CODE 2018

Schedule B - Continued

Building Permit Number
(for authority having jurisdiction's use)

9090 Island Highway, Chemainus, BC

Project Address

Geotechnical
Discipline

The undersigned also undertakes to notify the *authority having jurisdiction* in writing as soon as possible if the undersigned's contract for *field review* is terminated at any time during construction.

I certify that I am a *registered professional* as defined in the British Columbia Building Code.

Kevin Bodnar, P. Eng.

Registered Professional of Record's Name (Print)

1779 West 75th Avenue

Address (Print)

Vancouver B.C. V6P 6P2

Address (Print) (continued)

(604) 439-0922

Phone Number



June 1, 2021

Date

(If the *Registered Professional of Record* is a member of a firm, complete the following.)

I am a member of the firm GeoPacific Consultants Ltd.

and I sign this letter on behalf of the firm.

(Print name of firm)

Note: The above letter must be signed by a *registered professional of record*, who is a *registered professional*. The British Columbia Building Code defines a *registered professional* to mean

- (a) a person who is registered or licensed to practise as an architect under the Architects Act, or
- (b) a person who is registered or licensed to practise as a professional engineer under the Engineers and Geoscientists Act.

CRP's Initials

BRITISH COLUMBIA BUILDING CODE 2018

Schedule B - Continued

Building Permit Number
(for authority having jurisdiction's use)

9090 Island Highway, Chemainus, BC
Project Address

Geotechnical
Discipline

SUMMARY OF DESIGN AND FIELD REVIEW REQUIREMENTS

(Initial applicable discipline below and cross out and initial only those items not applicable to the project.)

ARCHITECTURAL

- 1.1 Fire resisting assemblies
- 1.2 *Fire separations* and their continuity
- 1.3 *Closures*, including tightness and operation
- 1.4 Egress systems, including *access to exit* within *suites* and *floor areas*
- 1.5 Performance and physical safety features (guardrails, handrails, etc.)
- 1.6 Structural capacity of architectural components, including anchorage and seismic restraint
- 1.7 Sound control
- 1.8 Landscaping, screening and site grading
- 1.9 Provisions for firefighting access
- 1.10 Access requirements for *persons with disabilities*
- 1.11 Elevating devices
- 1.12 Functional testing of architecturally related fire emergency systems and devices
- 1.13 Development Permit and conditions therein
- 1.14 Interior signage, including acceptable materials, dimensions and locations
- 1.15 Review of all applicable shop drawings
- 1.16 Interior and exterior finishes
- 1.17 Dampproofing and/or waterproofing of walls and slabs below grade
- 1.18 Roofing and flashings
- 1.19 Wall cladding systems
- 1.20 Condensation control and cavity ventilation
- 1.21 Exterior glazing
- 1.22 Integration of building envelope components
- 1.23 Environmental separation requirements (Part 5)
- 1.24 Building envelope, Part 10 – ASHRAE, NECB or Energy Step Code requirements
- 1.25 Building envelope, testing, confirmation or both as per Part 10 requirements



June 1, 2021

Date

STRUCTURAL

- 2.1 Structural capacity of structural components of the *building*, including anchorage and seismic restraint
- 2.2 Structural aspects of *deep foundations*
- 2.3 Review of all applicable shop drawings
- 2.4 Structural aspects of unbonded post-tensioned concrete design and construction

MECHANICAL

- 3.1 HVAC systems and devices, including high *building* requirements where applicable
- 3.2 *Fire dampers* at required *fire separations*
- 3.3 Continuity of *fire separations* at HVAC penetrations
- 3.4 Functional testing of mechanically related fire emergency systems and devices
- 3.5 Maintenance manuals for mechanical systems
- 3.6 Structural capacity of mechanical components, including anchorage and seismic restraint
- 3.7 Review of all applicable shop drawings
- 3.8 Mechanical systems, Part 10 – ASHRAE, NECB or Energy Step Code requirements
- 3.9 Mechanical systems, testing, confirmation or both as per Part 10 requirements

CRP's Initials

BRITISH COLUMBIA BUILDING CODE 2018

Schedule B - Continued

Building Permit Number
(for authority having jurisdiction's use)

9090 Island Highway, Chemainus, BC

Project Address

Geotechnical

Discipline

PLUMBING

- 4.1 Roof drainage systems
- 4.2 Site and foundation drainage systems
- 4.3 Plumbing systems and devices
- 4.4 Continuity of fire separations at plumbing penetrations
- 4.5 Functional testing of plumbing related fire emergency systems and devices
- 4.6 Maintenance manuals for plumbing systems
- 4.7 Structural capacity of plumbing components, including anchorage and seismic restraint
- 4.8 Review of all applicable shop drawings
- 4.9 Plumbing systems, Part 10 – ASHRAE, NECB or Energy Step Code requirements
- 4.10 Plumbing systems, testing, confirmation or both as per Part 10 requirements

FIRE SUPPRESSION SYSTEMS

- 5.1 Suppression system classification for type of occupancy
- 5.2 Design coverage, including concealed or special areas
- 5.3 Compatibility and location of electrical supervision, ancillary alarm and control devices
- 5.4 Evaluation of the capacity of city (municipal) water supply versus system demands and domestic demand, including pumping devices where necessary
- 5.5 Qualification of welder, quality of welds and material
- 5.6 Review of all applicable shop drawings
- 5.7 Acceptance testing for "Contractor's Material and Test Certificate" as per NFPA Standards
- 5.8 Maintenance program and manual for suppression systems
- 5.9 Structural capacity of sprinkler components, including anchorage and seismic restraint
- 5.10 For partial systems — confirm sprinklers are installed in all areas where required
- 5.11 Fire Department connections and hydrant locations
- 5.12 Fire hose standpipes
- 5.13 Freeze protection measures for fire suppression systems
- 5.14 Functional testing of fire suppression systems and devices

ELECTRICAL

- 6.1 Electrical systems and devices, including high building requirements where applicable
- 6.2 Continuity of fire separations at electrical penetrations
- 6.3 Functional testing of electrical related fire emergency systems and devices
- 6.4 Electrical systems and devices maintenance manuals
- 6.5 Structural capacity of electrical components, including anchorage and seismic restraint
- 6.6 Clearances from buildings of all electrical utility equipment
- 6.7 Fire protection of wiring for emergency systems
- 6.8 Review of all applicable shop drawings
- 6.9 Electrical systems, Part 10 – ASHRAE, NECB or Energy Step Code requirements
- 6.10 Electrical systems, testing, confirmation or both as per Part 10 requirements

GEOTECHNICAL — Temporary

- 7.1 Excavation
- 7.2 Shoring
- 7.3 Underpinning
- 7.4 Temporary construction dewatering

GEOTECHNICAL — Permanent

- 8.1 Bearing capacity of the soil
- 8.2 Geotechnical aspects of deep foundations
- 8.3 Compaction of engineered fill
- 8.4 Structural considerations of soil, including slope stability and seismic loading
- 8.5 Backfill
- 8.6 Permanent dewatering
- 8.7 Permanent underpinning



June 1, 2021

Date

CRP's Initials



BFL CANADA Insurance Services Inc.
 1177 West Hastings Street, Suite 200
 Vancouver BC V6E 2K3
 Tel: 604-669-9600
 Toll Free: 1-866-669-9602
 Fax: 604-683-9316

Certificate of Insurance**Certificate No: 2021-00002**This is to certify to: **To Whom It May Concern**

that the following described policy(ies) or cover note(s) in force at this date have been affected to cover as shown below:


Named Insured: **Geopacific Consultants Ltd.**Address: **1779 West 75th Avenue, Vancouver, BC V6P 6P2**Description of operations and/or activities and/or locations to which this certificate applies: **Engineering and Surveying**

Type	Insurer / Policy No.	Policy Period from (mm/dd/yyyy) to (mm/dd/yyyy)	Limits
General Liability	Intact Insurance Company of Canada Policy No: 5A1197902	01/24/2021 to 01/24/2022	
Bodily Injury and Property Damage			\$ 5,000,000
Per Occurrence			\$ 5,000,000
Personal & Advertising Injury			\$ 5,000,000
Non Owned Automobile Liability			\$ 5,000,000
Products/Completed Operations Aggregate			\$ 500,000
Tenants Legal Liability			\$ 1,000
Deductible			
PARTICULARS OF INSURANCE - General Liability			
Premises Property and Operations, Products and Completed Operations, Cross Liability, Blanket Contractual (all written agreements), Occurrence Bodily Injury and Property Damage, Broad Form Property Damage, Contingent Employers Liability, Cross Liability and Separation of Insureds, Advertising and Personal Injury, Limited Pollution Liability Coverage Endorsement			
Professional Liability (Claims Made)	Victor Insurance Managers Inc. Policy No.ENG565081	01/24/2021 to 01/24/2022	
Each Claim			\$ 2,000,000
Aggregate			\$ 2,000,000
Deductible			\$ 25,000

Additional Information

This certificate is issued as a matter of information only and is subject to all the limitations, exclusions and conditions of the above-listed policies as they now exist or may hereafter be endorsed. We accept no responsibility whatsoever for any inadvertent or negligent act, error or omission on our part in preparing these statements or for any loss, damage or expense thereby occasioned to any recipient of this certificate.

Limits shown above may be reduced by Claims or Expenses paid. This Policy contains a Clause(s) which may limit the amount payable.

BFL CANADA Insurance Services Inc.

 Authorized Representative

Jeff McLellan

Signed in Vancouver this January 22, 2021

ENGINEER OF RECORD – RETAINING WALL ASSURANCE STATEMENT

Note: This Assurance Statement must be completed, signed, and sealed by an individual who:

- (i) is a professional engineer or licensee registered or licensed by the Association of Professional Engineers and Geoscientists of the Province of British Columbia (the "Association");
- (ii) has read the Association's *Professional Practice Guidelines – Retaining Wall Design* (the "Guidelines"), and has considered the guidance provided in the Guidelines;
- (iii) is qualified by education, training, and experience to serve as "Engineer of Record", as that term is defined in the Guidelines; and
- (iv) has undertaken responsibility for the project described below in the capacity of Engineer of Record.

[Print clearly and legibly]

TO: **OWNER / CLIENT**

DATE: November 20, 2023

1251719 BC Ltd.

Name

320 - 8988 Fraserton Court

Address

Burnaby, BC V5J 5H8

FOR: **PROJECT**

ROCK RETAINING WALLS

MORGAN MAPLES MODULAR HOME DEVELOPMENT

9090 TRANS CANADA HIGHWAY, CHEMAINUS, BC

ENGINEER OF RECORD – RETAINING WALL ASSURANCE STATEMENT

In preparing the Retaining Wall design, I confirm that the following tasks have been completed:

RETAINING WALL CHECKLIST

General (all Retaining Walls):

Check that the following items have been addressed:

- ☒ 1. Reviewed requirements of the governing jurisdiction, and documented all other codes, specifications, and guidelines used.
- ☒ 2. Established design criteria based on applicable codes and confirmed criteria with owner.
- ☒ 3. Completed a site assessment to determine site factors to be incorporated into the Retaining Wall design and construction.
- ☒ 4. Conducted geotechnical investigation to determine site conditions and appropriate geotechnical parameters for analysis and design.
- ☒ 5. Determined external loading conditions (for example, traffic and construction surcharge loads, potential scour, or flooding).
- ☒ 6. Provided lateral earth pressures recommendations for static and seismic loading (these will vary based on the type of wall used).
- ☒ 7. Analyzed static global stability of slope – minimum factor of safety >1.5 for N! cases where N is the number of terraces
- ☒ 8. Analyzed seismic global stability of slope, if applicable – minimum factor of safety 1.1 or acceptable wall displacement
- ☒ 9. Assessed liquefaction potential (provided mitigation measures, if applicable).
- ☒ 10. Provided recommendations for general site and wall drainage.
- ☒ 11. Provided recommendations for erosion protection, Slope Protection/Wall Facing.
- ☒ 12. Assessed the potential impact of wall construction on the slopes above and below the wall.
- ☒ 13. Assessed the potential impact of the wall on adjacent structures.

Gravity Walls:

Check that the following items have been addressed:

- ☐ 1. Analyzed for overturning, sliding, and bearing capacity under static conditions.
- ☐ 2. Analyzed for overturning, sliding, and bearing capacity under seismic conditions, if applicable.
- ☐ 3. Completed internal design of the wall (structural design).
- ☐ 4. Detailed an adequate drainage system.
- ☐ 5. Provided appropriate information and guidance for wall construction, including placement specifications, temporary slopes, drainage works, quality control requirements.

ENGINEER OF RECORD – RETAINING WALL ASSURANCE STATEMENT

Retaining Wall Checklist
Page 2

Stacked Rock Walls:

Check that the following items have been addressed:

- ☒ 1. Analyzed for overturning, sliding, and bearing capacity under static conditions.
- ☒ 2. Analyzed internal stability, including sliding between rocks at different heights within the wall.
- ☒ 3. Analyzed for overturning, sliding, and bearing capacity under seismic conditions, if applicable.
- ☒ 4. Detailed an adequate drainage system.
- ☒ 5. Demonstrated by previous performance or laboratory testing that the rock proposed for use in the wall will be durable.
- ☒ 6. Provided appropriate information and guidance for wall construction, including placement specifications, rock sizes/weights and stacking requirements, temporary slopes, drainage works, quality control requirements.

Mechanically Stabilized Earth Walls:

Check that the following items have been addressed:

- ☐ 1. Analyzed for overturning, sliding, and bearing capacity and internal stability under static conditions.
- ☐ 2. Analyzed for overturning, sliding, and bearing capacity and internal stability under seismic conditions, if applicable.
- ☐ 3. Analyzed the adequacy of the wall facing to withstand applicable loads, including the loads from connections to soil reinforcement.
- ☐ 4. Provided specifications for soil reinforcement.
- ☐ 5. Confirmed that minimum soil reinforcement length is 70% of the wall height, or provided justification for alternate length.
- ☐ 6. Detailed an adequate drainage system.
- ☐ 7. Provided appropriate information and guidance for wall construction, including placement specifications, temporary slopes, drainage works, quality control requirements.

Reinforced Concrete Cantilever Retaining Walls:

Check that the following items have been addressed:

- ☐ 1. Analyzed for overturning, sliding, and bearing capacity under static conditions.
- ☐ 2. Analyzed for overturning, sliding, and bearing capacity under seismic conditions, if applicable.
- ☐ 3. Completed internal design of the wall (structural design).
- ☐ 4. Detailed an adequate drainage system.
- ☐ 5. Provided appropriate information and guidance for wall construction, including placement specifications, temporary slopes, drainage works, quality control requirements.

ENGINEER OF RECORD – RETAINING WALL ASSURANCE STATEMENT

Retaining Wall Checklist
Page 3

Submittals:

Check that the following items have been addressed:

- ☒ 1. Site plan showing wall location; wall footprint; existing and proposed ground slopes behind and in front of wall; locations of roads, structures, utilities, and all other facilities in the vicinity of the wall; and locations of the wall foundation drainage and other appurtenant drains, including associated discharge locations.
- ☐ 2. Profile along the length of the wall showing variations in wall height, fill height behind the wall, invert elevations of wall foundation drains, and all other features that are included in the design or in close proximity to the wall.
- ☒ 3. Cross-section showing typical wall details, including wall batter, foundation preparation, leveling pad details, drainage provisions, erosion protection of exposed slopes above the wall, guardrail details (if required), and other features that are included in the wall design.
- ☒ 4. Specifications for backfill and retained soil gradation and all other materials to be incorporated into the Retaining Wall (i.e., geosynthetics, concrete, anchors, drainage media), placement and compaction requirements, field review and compaction testing to meet stability and performance design requirements, drains, erosion control during construction, and concrete, reinforcement, and other structural components.
- ☐ 5. Monitoring and maintenance plan, if applicable.

Field Reviews:

Check that the following item has been addressed:

- ☒ 1. The obligation for field reviews as per Bylaw 14(b)(3) has been fulfilled to ascertain whether the implementation or construction of the work substantially complies in all material respects with the design.

ENGINEER OF RECORD – RETAINING WALL ASSURANCE STATEMENT

I certify that I am a professional engineer or licensee registered or licensed by the Association, that I am qualified to serve as Engineer of Record as defined in the Guidelines, and that I have undertaken responsibility for this project in the capacity of Engineer of Record.

Chris Hudec, M.A.Sc., P.Eng.

Name (print)



Signature

November 20, 2023

Date

1900 Boxwood Road

Address

Nanaimo, BC V9S 5Y2

250-756-0355

Phone

geotech@lewkowich.com

Email

(Affix Professional seal here)

If the Engineer of Record is a member of a firm, complete the following:

I am a member of the firm Lewkowich Engineering Associates Ltd., P2P No. 1001802
and I sign this letter on behalf of the firm. (Print name of firm)

BRITISH COLUMBIA BUILDING CODE 2018

SCHEDULE B

Forming Part of Subsection 2.2.7., Division C of the
British Columbia Building CodeBuilding Permit Number
(for authority having jurisdiction's use)ASSURANCE OF PROFESSIONAL DESIGN AND
COMMITMENT FOR FIELD REVIEW

- Notes: (i) This letter must be submitted prior to the commencement of construction activities of the components identified below. A separate letter must be submitted by each *registered professional of record*.
(ii) This letter is endorsed by: Architectural Institute of BC, Association of Professional Engineers and Geoscientists of the Province of BC, Building Officials' Association of BC, and Union of BC Municipalities.
(iii) In this letter the words in italics have the same meaning as in the British Columbia Building Code.

To: The authority having jurisdiction

MUNICIPALITY OF NORTH COWICHAN

Name of Jurisdiction (Print)

Re: STACKED ROCK RETAINING WALLS (E2286)

Name of Project (Print)

9090 TRANS CANADA HIGHWAY (PID: 009-885-200)

Address of Project (Print)

PERMIT TO PRACTICE NUMBER: 1001802

The undersigned hereby gives assurance that the design of the

(Initial those of the items listed below that apply to this *registered professional of record*. All the disciplines will not necessarily be employed on every project.)

<input checked="" type="checkbox"/>	ARCHITECTURAL
<input checked="" type="checkbox"/>	STRUCTURAL
<input checked="" type="checkbox"/>	MECHANICAL
<input checked="" type="checkbox"/>	PLUMBING
<input checked="" type="checkbox"/>	FIRE SUPPRESSION SYSTEMS
<input checked="" type="checkbox"/>	ELECTRICAL
<input checked="" type="checkbox"/>	GEOTECHNICAL — temporary
CMH	GEOTECHNICAL — permanent



(Professional's Seal and Signature)

NOVEMBER 15, 2023

Date

components of the plans and supporting documents prepared by this *registered professional of record* in support of the application for the *building* permit as outlined below substantially comply with the British Columbia Building Code and other applicable enactments respecting safety except for construction safety aspects.

The undersigned hereby undertakes to be responsible for *field reviews* of the above referenced components during construction, as indicated on the "SUMMARY OF DESIGN AND FIELD REVIEW REQUIREMENTS" below.

CRP's Initials

Schedule B - Continued

Building Permit Number
(for authority having jurisdiction's use)

9090 TRANS CANADA HIGHWAY (PID: 009-885-200)

Project Address

GEOTECHNICAL

Discipline

The undersigned also undertakes to notify the *authority having jurisdiction* in writing as soon as possible if the undersigned's contract for *field review* is terminated at any time during construction.

I certify that I am a *registered professional* as defined in the British Columbia Building Code.

CHRIS HUDEC, P.ENG.

Registered Professional of Record's Name (Print)

1900 BOXWOOD ROAD

Address (Print)

NANAIMO, BC V9S 5Y2

Address (Print) (continued)

250-756-0355

Phone Number

PERMIT TO PRACTICE NUMBER: 1001802



(Professional's Seal and Signature)

NOVEMBER 15, 2023

Date

(If the *Registered Professional of Record* is a member of a firm, complete the following.)

I am a member of the firm LEWKOWICH ENGINEERING ASSOCIATES LTD.
and I sign this letter on behalf of the firm. (Print name of firm)

Note: The above letter must be signed by a *registered professional of record*, who is a *registered professional*. The British Columbia Building Code defines a *registered professional* to mean

- (a) a person who is registered or licensed to practise as an architect under the Architects Act, or
- (b) a person who is registered or licensed to practise as a professional engineer under the Engineers and Geoscientists Act.

CRP's Initials

BRITISH COLUMBIA BUILDING CODE 2018

Schedule B - Continued

Building Permit Number
(for authority having jurisdiction's use)

9090 TRANS CANADA HIGHWAY (PID: 009-885-200)

Project Address

GEOTECHNICAL

Discipline

SUMMARY OF DESIGN AND FIELD REVIEW REQUIREMENTS

(Initial applicable discipline below and cross out and initial only those items not applicable to the project.)

ARCHITECTURAL

- 1.1 Fire resisting assemblies
- 1.2 *Fire separations* and their continuity
- 1.3 *Closures*, including tightness and operation
- 1.4 Egress systems, including *access to exit* within *suites* and *floor areas*
- 1.5 Performance and physical safety features (guardrails, handrails, etc.)
- 1.6 Structural capacity of architectural components, including anchorage and seismic restraint
- 1.7 Sound control
- 1.8 Landscaping, screening and site grading
- 1.9 Provisions for firefighting access
- 1.10 Access requirements for *persons with disabilities*
- 1.11 Elevating devices
- 1.12 Functional testing of architecturally related fire emergency systems and devices
- 1.13 Development Permit and conditions therein
- 1.14 Interior signage, including acceptable materials, dimensions and locations
- 1.15 Review of all applicable shop drawings
- 1.16 Interior and exterior finishes
- 1.17 Dampproofing and/or waterproofing of walls and slabs below *grade*
- 1.18 Roofing and flashings
- 1.19 Wall cladding systems
- 1.20 Condensation control and cavity ventilation
- 1.21 Exterior glazing
- 1.22 Integration of building envelope components
- 1.23 Environmental separation requirements (Part 5)
- 1.24 Building envelope, Part 10 – ASHRAE, NECB or Energy Step Code requirements
- 1.25 Building envelope, testing, confirmation or both as per Part 10 requirements

PERMIT TO PRACTICE NUMBER: 1001802



(Professional's Seal and Signature)

NOVEMBER 15, 2023

Date

STRUCTURAL

- 2.1 Structural capacity of structural components of the *building*, including anchorage and seismic restraint
- 2.2 Structural aspects of *deep foundations*
- 2.3 Review of all applicable shop drawings
- 2.4 Structural aspects of unbonded post-tensioned concrete design and construction

MECHANICAL

- 3.1 HVAC systems and devices, including high *building* requirements where applicable
- 3.2 *Fire dampers* at required *fire separations*
- 3.3 Continuity of *fire separations* at HVAC penetrations
- 3.4 Functional testing of mechanically related fire emergency systems and devices
- 3.5 Maintenance manuals for mechanical systems
- 3.6 Structural capacity of mechanical components, including anchorage and seismic restraint
- 3.7 Review of all applicable shop drawings
- 3.8 Mechanical systems, Part 10 – ASHRAE, NECB or Energy Step Code requirements
- 3.9 Mechanical systems, testing, confirmation or both as per Part 10 requirements

CRP's Initials

Schedule B - Continued

Building Permit Number
(for authority having jurisdiction's use)

9090 TRANS CANADA HIGHWAY (PID: 009-885-200)

Project Address

GEOTECHNICAL

Discipline

PLUMBING

- ~~4.1 Roof drainage systems~~
- ~~4.2 Site and foundation drainage systems~~
- ~~4.3 Plumbing systems and devices~~
- ~~4.4 Continuity of fire separations at plumbing penetrations~~
- ~~4.5 Functional testing of plumbing related fire emergency systems and devices~~
- ~~4.6 Maintenance manuals for plumbing systems~~
- ~~4.7 Structural capacity of plumbing components, including anchorage and seismic restraint~~
- ~~4.8 Review of all applicable shop drawings~~
- ~~4.9 Plumbing systems, Part 10 - ASHRAE, NECB or Energy Step Code requirements~~
- ~~4.10 Plumbing systems, testing, confirmation or both as per Part 10 requirements~~

FIRE SUPPRESSION SYSTEMS

- 5.1 Suppression system classification for type of occupancy
- 5.2 Design coverage, including concealed or special areas
- 5.3 Compatibility and location of electrical supervision, ancillary alarm and control devices
- 5.4 Evaluation of the capacity of city (municipal) water supply versus system demands and domestic demand, including pumping devices where necessary
- 5.5 Qualification of welder, quality of welds and material
- 5.6 Review of all applicable shop drawings
- 5.7 Acceptance testing for "Contractor's Material and Test Certificate" as per NFPA Standards
- 5.8 Maintenance program and manual for suppression systems
- 5.9 Structural capacity of sprinkler components, including anchorage and seismic restraint
- 5.10 For partial systems — confirm sprinklers are installed in all areas where required
- 5.11 Fire Department connections and hydrant locations
- 5.12 Fire hose standpipes
- 5.13 Freeze protection measures for fire suppression systems
- 5.14 Functional testing of fire suppression systems and devices

ELECTRICAL

- 6.1 Electrical systems and devices, including high building requirements where applicable
- 6.2 Continuity of fire separations at electrical penetrations
- 6.3 Functional testing of electrical related fire emergency systems and devices
- 6.4 Electrical systems and devices maintenance manuals
- 6.5 Structural capacity of electrical components, including anchorage and seismic restraint
- 6.6 Clearances from buildings of all electrical utility equipment
- 6.7 Fire protection of wiring for emergency systems
- 6.8 Review of all applicable shop drawings
- 6.9 Electrical systems, Part 10 - ASHRAE, NECB or Energy Step Code requirements
- 6.10 Electrical systems, testing, confirmation or both as per Part 10 requirements

GEOTECHNICAL — Temporary

- 7.1 Excavation
- 7.2 Shoring
- 7.3 Underpinning
- 7.4 Temporary construction dewatering

CMH GEOTECHNICAL — Permanent

- 8.1 Bearing capacity of the soil
- ~~8.2 Geotechnical aspects of deep foundations~~
- 8.3 Compaction of engineered fill
- 8.4 Structural considerations of soil, including slope stability and seismic loading
- ~~8.5 Backfill~~
- ~~8.6 Permanent dewatering~~
- ~~8.7 Permanent underpinning~~

PERMIT TO PRACTICE NUMBER: 1001802



(Professional's Seal and Signature)

NOVEMBER 15, 2023

Date

CRP's Initials